

**East Montpelier, TH 47, Murray Road over Brook**

**Remove 48"RCP and Install New 10'-9" x 6'-10" x 46'-6" Plate Pipe Arch**

<b>Item No.</b>	<b>Item Name</b>	<b>Quantity</b>	<b>Unit</b>	<b>Unit Price</b>	<b>Total</b>
201.10	Clearing and Grubbing Incl. Individual Trees and Stumps	1	LUMP SUM	\$	\$
203.15	Common Excavation	115	CY	\$	\$
203.27	Unclassified Channel Excavation	25	CY	\$	\$
204.25	Structure Excavation	240	CY	\$	\$
204.30	Granular Backfill for Structures	230	CY	\$	\$
301.15	Subbase of Gravel	145	CY	\$	\$
401.10	Aggregate Surface Course	65	CY	\$	\$
529.15	Removal of Structure	1	EACH	\$	\$
608.25	All Purpose Excavator Rental, Type 1	6	Hours	\$	\$
613.11	Stone Fill, Type II	25	CY	\$	\$
621.20	Steel Beam Guard Rail, Galvanized	283	LF	\$	\$
621.206	Steel Beam Guardrail, Galvanized/Nested	12.5	LF	\$	\$
621.60	Anchor for Steel Beam Rail	4	EACH	\$	\$
621.80	Removal and Disposal of Guard Rail	145	LF	\$	\$
635.11	Mobilization/Demobilization	1	LUMP SUM	\$	\$
641.10	Traffic Control	1	LUMP SUM	\$	\$
649.11	Geotextile for Roadbed Separator	89	SY	\$	\$
649.31	Geotextile Under Stone Fill	48	SY	\$	\$
651.40	Grubbing Material	30	SY	\$	\$
	Erosion Prevention and Sediment Control	1	LUMP SUM	\$	\$
	Temporary Stream Diversion	1	LUMP SUM	\$	\$
	Streambed Stone Fill, Type E2	31	CY	\$	\$
	Assembly of New Structure	1	LUMP SUM	\$	\$
	Installation of New Structure	1	LUMP SUM	\$	\$
	Turf Establishment (Seed, Fertilizer, Mulch, etc.)	1	LUMP SUM	\$	\$
				<b>Total</b>	<b>\$</b>