

East Montpelier, TH 7 (Quaker Road) over Brook

New 66" x 61' Corrugated Aluminum Pipe with Reinforced Concrete Headwalls

Item No.	Item Name	Quantity	Unit	Unit Price	Total
201.10	Clearing and Grubbing Incl. Individual Trees and Stumps	1	LUMP SUM	\$	\$
203.15	Common Excavation	297	CY	\$	\$
203.27	Unclassified Channel Excavation	25	CY	\$	\$
203.28	Excavation of Surfaces and Pavements	27	CY	\$	\$
204.25	Structure Excavation	287	CY	\$	\$
204.30	Granular Backfill for Structures	210	CY	\$	\$
210.10	Cold Planing, Bituminous Pavement	78	SY	\$	\$
301.35	Subbase of Dense Graded Crushed Stone	460	CY	\$	\$
406.25	Bituminous Concrete Pavement	70	TON	\$	\$
501.34	Concrete, High Performance Class B	19	CY	\$	\$
507.15	Reinforcing Steel	2,241	LBS	\$	\$
514.10	Water Repellent, Silane	10	GAL	\$	\$
608.25	All Purpose Excavator Rental, Type I	20	HOURS	\$	\$
613.11	Stone Fill, Type II	30	CY	\$	\$
617.10	Relocate Mailbox, Single Support	1	EACH	\$	\$
621.205	Steel Beam Guard Rail, Galvanized with 8' Posts	658	LF	\$	\$
621.60	Anchor for Steel Beam Guard Rail	4	EACH	\$	\$
635.11	Mobilization/Demobilization	1	LUMP SUM	\$	\$
641.10	Traffic Control	1	LUMP SUM	\$	\$
646.20	4" White Line	800	LF	\$	\$
646.21	4" Yellow Line	800	LF	\$	\$
649.11	Geotextile for Roadbed Separator (for use under new pipe)	63	SY	\$	\$
649.31	Geotextile Under Stone Fill	65	SY	\$	\$
651.40	Grubbing Material	20	SY	\$	\$
				\$	\$
	Erosion Prevention and Sediment Control	1	LUMP SUM	\$	\$
	Temporary Stream Diversion	1	LUMP SUM	\$	\$
	Streambed Stone Fill, Type EI	9	CY	\$	\$
	Installation of New Structure	1	LUMP SUM	\$	\$
	Turf Establishment (Seed, Fertilizer, Mulch, etc.)	1	Lump Sum	\$	\$
				Total	
	Aluminum Pipe Culvert Will Be Provided By Town				