VTRANS STANDARDS 06/01/1994 SLOPE GRADING, EMBANKMENTS, MUCK 07/08/2005 STANDARD FOR RESIDENTIAL AND COMMERCIAL DRIVES 02/11/2008 C-10 CURBING 10/14/2005 PORTLAND CEMENT CONCRETE SIDEWALK DRIVE C-2A ENTRANCES WITH SIDEWALK ADJACENT TO CURB PORTLAND CEMENT CONCRETE SIDEWALK DRIVE 10/14/2005 ENTRANCES WITH SIDEWALK AND GREEN STRIP SIDEWALK RAMPS 03/10/2008 C-3A SIDEWALK RAMPS AND MEDIAN ISLANDS 03/10/2008 C-3B D – 1 PRECAST REINFORCED CONCRETE DROP INLET 06/01/1994 DETAILS PRECAST REINF CONC. MH-GRATES, CAST IRON 06/01/1994 GRATE WITH FRAME, TYPE D & E STANDARD SIGN PLACEMENT - CONVENTIONAL ROAD 08/08/1995 ROUTE MARKINGS AT RURAL INTERSECTIONS 08/08/1995 08/08/1995 STATE ROUTE MARKER SIGN DETAILS 12/23/1994 E-145A REGULATORY SIGN DETAILS - LANE USE CONTROL SIGNS TRAFFIC CONTROL SIGNALS PEDESTAL POST E-170 11/04/1999 MOUNTED E-171A TRAFFIC CONTROL SIGNALS GENERAL NOTES & 08/09/1995 DETAILS PAVEMENT MARKING DETAILS 02/01/1999 08/18/1995 E-193 PAVEMENT MARKING DETAILS T – I TRAFFIC CONTROL GENERAL NOTES 04/25/2016 TRAFFIC SIGN GENERAL NOTES 04/25/2016 T-2 08/06/2012 T-10 CONVENTIONAL ROADS CONSTRUCTION APPROACH SIGNING TRAFFIC CONTROL FOR MAINTENANCE PAVEMENT T-24 08/06/2012 MARKING OPERATION T-28 08/06/2012 CONSTRUCTION SIGN DETAILS 08/06/2012 T-29 CONSTRUCTION SIGN DETAILS T-30 CONSTRUCTION SIGN DETAILS 08/06/2012 08/06/2012 T - 3 I CONSTRUCTION SIGN DETAILS T-36 CONSTRUCTION ZONE LONGITUDINAL DROP-OFFS FOR 08/06/2012 PAVING T-45 SQUARE TUBE SIGN POST AND ANCHOR 01/02/2013 10/26/2015 T-56 STANDARD SIGN PLACEMENT 10/26/2015 ROUTE MARKER FRAME DETAILS T-92 DESTINATION SIGN DETAILS 10/26/2015 T-93 INDEX OF SHEETS TITLE SHEET CONVENTIONAL SYMBOLOGY LEGEND SHEET 3 PROJECT NOTES SHEET 4-6 TYPICAL SECTION SHEETS 1-3 7 - 9 DETAIL SHEETS 1-3 TIE SHEET 10 ALIGNMENT SHEET QUANTITY SHEETS 1-2 12-13 RIGHT OF WAY DETAIL SHEETS 1-3 RIGHT OF WAY PLAN SHEETS 1-2 PROJECT LAYOUT SHEETS 1-2 19-20 SIGN AND MARKINGS LAYOUT SHEETS 1-2 23 EPSC NARRATIVE 24 EPSC LEGEND AND NOTES SHEET EPSC EXISTING CONDITIONS PLAN SHEETS 1-2 27-28 EPSC CONSTRUCTION CONDITIONS PLAN SHEETS 1-2 EPSC FINAL CONDITIONS PLAN SHEETS 1-2 31-33 EPSC DETAILS SHEETS 1-3 34-35 TRAFFIC SIGN SUMMARY SHEETS 1-2 36-39 CROSS SECTION SHEETS 1-4 CONSTRUCTION APPROACH SIGNING SHEET PHASING TYPICAL SECTIONS 1-2 41-42 TRAFFIC CONTROL NOTES SHEETS 1-2 43-44 QUALITY ASSURANCE PROGRAM: LEVEL 3 SURVEYED BY : DuBOIS & KING, INC.



PROPOSED IMPROVEMENT

OF EAST MONTPELIER COUNTY OF WASHINGTON VILLAGE SAFETY IMPROVEMENT PROJECT (PRINCIPAL ARTERIAL)

PROJECT LOCATION: VT ROUTE 14 AND US ROUTE 2 CORRIDOR IN EAST MONTPELIER VILLAGE BETWEEN THE SOUTHERN AND NORTHERN INTERSECTIONS OF VT ROUTE 14

PROJECT DESCRIPTION: WORK TO BE PERFORMED UNDER THIS PROJECT INCLUDES PORTLAND CEMENT CONCRETE SIDEWALKS, VERTICAL GRANITE CURBING, PAVEMENT STRIPING, GRADING, SIGNING, DRAINAGE MODIFICATIONS, AND OTHER HIGHWAY RELATED ITEMS

LENGTH OF SIDEWALK : 1091.65 FEET (0.207 MI)

LENGTH OF PROJECT : 926.70 FEET (0.176 MI.)

TRAFFIC DATA													
LLICHWAY SECTION	АА	AADT		DHV		ХΤ		%D		TT	CUM. ESALS	CUM. ESALS	
HIGHWAY SECTION		2029	2019	2029	2019	2029	2019	2029	2019	2029	(2019-2029)	(2019-2039)	
U.S. 2 MM 2.7250 - MM 2.9650	13500	14100	1500	1600	7.5	9. 1	59	59	1100	1400	3,447,000	7,822,000	
POSTED & DESIGN SPEED													

MONTPELIER

LOCATION MAP

NOT TO SCALE

24)

35 MPH END SIDEWALK BEGIN SIDEWALK -STA. N 13+59.23 STA. N 16+09.19 -BEGIN PROJECT BEGIN SIDEWALK - END SIDEWALK STA N 9+93.70 STA N 17+44.87 10+00 N 11+00 N 12+00 N 13+00 N 14+00 N US ROUTE 2 / VT ROUTE 14 S 19+00 S 20+00 S 21+00 S 22+00 -5 23+00 BEGIN SIDEWALK STA S 19+88.99 END PROJECT END SIDEWALK STA. S 25+79.43

SCALE I'' = 100'-0"

PLANS.

SURVEYED DATE: JULY 21, 2014

DATUM GPS DERIVED

> VERTICAL NAVD 88 HORIZONTAL NAV 83 (92)





FOR BIDDING PURPOSES ONLY

CONSTRUCTION IS TO BE CARRIED ON IN ACCORDANCE WITH THESE PLANS AND THE STANDARD SPECIFICATIONS FOR CONSTRUCTION DATED 2018, AS APPROVED BY THE FEDERAL HIGHWAY ADMINISTRATION ON APRIL 13, 2018 FOR USE ON THIS PROJECT, INCLUDING ALL SUBSEQUENT REVISIONS AND SUCH REVISED SPECIFICATIONS AND SPECIAL PROVISIONS AS ARE INCORPORATED IN THESE

BELIEVED TO BE ACCURATE BUT SHOULD NOT BE RELIED UPON FOR PURPOSES UNRELATED TO THE TOWN OF EAST MONTPELIER'S ACQUISITION OF LAND AND RIGHTS FOR THIS PROJECT.

LINES SHOWN ON THIS PLAN AS EXISTING PROPERTY LINES P/L ARE

CANADA

State of

NEW HAMPSHIRE

ADDISON

いた RUTLAND

WINDHAM

Commonwealth of

MASSACHUSETTS

State of

NEW YORK

EAST MONTPELIER VILLAGE SAFETY IMPROVEMENT

PROJECT

STP BIKE (63)

TOWN OF EAST MONTPELIER TOWN MANAGER

APPROVED_ _ DATE _

PROJECT MANAGER : BRIAN M. BRESLEND, P.E.

EAST MONTPELIER VILLAGE SAFETY IMPROVEMENT PROJECT PROJECT NAME

PROJECT NUMBER : STP BIKE (63)

SHEET I OF 44

DISCLAIMER

GENERAL INFORMATION

SYMBOLOGY LEGEND NOTE

THE SYMBOLOGY ON THIS SHEET IS INTENDED TO COVER STANDARD CONVENTIONAL SYMBOLOGY. THE SYMBOLOGY IS USED FOR EXISTING & PROPOSED FEATURES WITH HEAVIER LINEWEIGHT, IN COMBINATION WITH PROJECT ANNOTATION, AS NOTED ON PROJECT PLAN SHEETS. THIS LEGEND SHEET COVERS THE BASICS. SYMBOLOGY ON PLANS MAY VARY, PLAN ANNOTATIONS AND NOTES SHOULD BE USED TO CLARIFY AS NEEDED.

R. O. W.	ABBREV	IATIONS (CODES) & SYMBOLS
POINT	CODE	DESCRIPTION
	СН	CHANNEL EASEMENT
	CONST	CONSTRUCTION EASEMENT
	CUL	CULVERT EASEMENT
	D&C	DISCONNECT & CONNECT
	DIT	DITCH EASEMENT
	DR	DRAINAGE EASEMENT
	DRIVE	DRIVEWAY EASEMENT
	EC	EROSION CONTROL
	1&M	INSTALL & MAINTAIN EASEMENT
	LAND	LANDSCAPE EASEMENT
	R&RES	REMOVE & RESET
	R&REP	REMOVE & REPLACE
	SR	SLOPE RIGHT
	UE	UTILITY EASEMENT
	(P)	PERMANENT EASEMENT
	(T)	TEMPORARY EASEMENT
	BNDNS	BOUND SET
	BNDNS	BOUND TO BE SET
	IPNS	IRON PIN SET
\odot	IPNS	IRON PIN TO BE SET
\boxtimes	CALC	EXISTING ROW POINT
\bigcirc	PROW	PROPOSED ROW POINT
[LENG	ТНТ	LENGTH CARRIED ON NEXT SHEET

COMMON TOPOGRAPHIC POINT SYMBOLS

POINT	CODE	DESCRIPTION
۸:۸ ۷:۷	APL	BOUND APPARENT LOCATION
•	BM	BENCH MARK
⊡	BND	BOUND
	СВ	CATCH BASIN
ф	COMB	COMBINATION POLE
	DITHR	DROP INLET THROATED DNC
ŗ	EL	ELECTRIC POWER POLE
⊙	FPOLE	FLAGPOLE
\odot	GASFIL	GAS FILLER
\odot	GP	GUIDE POST
×	GSO	GAS SHUT OFF
⊙	GUY	GUY POLE
⊙	GUYW	GUY WIRE
×	GV	GATE VALVE
	Н	TREE HARDWOOD
Δ	HCTRL	CONTROL HORIZONTAL
\triangle	HVCTRL	CONTROL HORIZ. & VERTICAL
••	HYD	HYDRANT
<a> 	IP	IRON PIN
⊗	IPIPE	IRON PIPE
,	LI	LIGHT - STREET OR YARD
\$	MB	MAILBOX
0	MH	MANHOLE (MH)
•	MM	MILE MARKER
⊖	PM	PARKING METER
•	PMK	PROJECT MARKER
©	POST	POST STONE/WOOD
	RRSIG	RAILROAD SIGNAL
•	RRSL	RAILROAD SWITCH LEVER
	S	TREE SOFTWOOD
- •	SAT	SATELLITE DISH
	SHRUB	SHRUB
$\overline{\circ}$	SIGN	SIGN
A	STUMP	STUMP
	TEL	TELEPHONE POLE
⊙	TIE	TIE
0.0	TSIGN	SIGN W/DOUBLE POST
\downarrow	VCTRL	CONTROL VERTICAL
0	WELL	WELL
M	WSO	WATER SHUT OFF

THESE ARE COMMON VAOT SURVEY POINT SYMBOLS FOR EXISTING FEATURES, ALSO USED FOR PROPOSED FEATURES WITH HEAVIER LINEWEIGHT, IN COMBINATION WITH PROPOSED ANNOTATION.

PROPOSED GEOMETRY CODES

1 1/01 031	LD GEOMETICE CODES
CODE	DESCRIPTION
PC	POINT OF CURVATURE
PI	POINT OF INTERSECTION
CC	CENTER OF CURVE
PT	POINT OF TANGENCY
PCC	POINT OF COMPOUND CURVE
PRC	POINT OF REVERSE CURVE
POB	POINT OF BEGINNING
POE	POINT OF ENDING
STA	STATION PREFIX
АН	AHEAD STATION SUFFIX
BK	BACK STATION SUFFIX
D	CURVE DEGREE OF (100FT)
R	CURVE RADUIS OF
T	CURVE TANGENT LENGTH
L	CURVE LENGTH OF
E	CURVE EXTERNAL DISTANCE

UTILITY SYMBOLOGY

UNDERGROUND UTILITIES — UT — · · - TELEPHONE — UE — · · - ELECTRIC — *UC* — · · - CABLE (TV) — UEC — · · · - ELECTRIC+CABLE — UET — · · - ELECTRIC+TELEPHONE — UCT — · · - CABLE+TELEPHONE - UECT - · · - ELECTRIC+CABLE+TELEP. — G — · · · - GAS LINE - W - · · - WATER LINE — S — -- - SANITARY SEWER (SEPTIC) ABOVE GROUND UTILITIES (AERIAL) — T — · · · - TELEPHONE — E — · · · - ELECTRIC — C — · · · - CABLE (TV) — EC — · · - ELECTRIC+CABLE — ET — · · - ELECTRIC+TELEPHONE - AER E&T - · · - · ELECTRIC+TELEPHONE — CT — · · - CABLE+TELEPHONE - ECT - · · - ELECTRIC+CABLE+TELEP. — · · · — · · · — UTILITY POLE GUY WIRE PROJECT CONSTRUCTION SYMBOLOGY

PROJECT DESIGN &	LAYOUT SYMBOLOGY
	CLEAR ZONE
	PLAN LAYOUT MATCHLINE

PROJECT CONSTRUCTION FEATURES

<u> </u>	TOP OF CUT SLOPE
0 0 0	TOE OF FILL SLOPE
8 8 8 8 8	STONE FILL
	BOTTOM OF DITCH &
= $=$ $=$ $=$	CULVERT PROPOSED
	STRUCTURE SUBSURFACE
PDFPDF	PROJECT DEMARCATION FENCE
$BF \xrightarrow{\times \times \times} BF \xrightarrow{\times \times}$	BARRIER FENCE
******	TREE PROTECTION ZONE (TPZ)
///////////////////////////////////////	STRIPING LINE REMOVAL


CONVENTIONAL BOUNDARY SYMBOLOGY

SHEET PILES


BOUNDARY LINES

TOWN LINE	TOWN BOUNDARY LINE
COUNTY LINE	COUNTY BOUNDARY LINE
STATE LINE	STATE BOUNDARY LINE
	PROPOSED STATE R.O.W. (LIMITED ACCESS)
	PROPOSED STATE R.O.W.
	STATE ROW (LIMITED ACCESS)
	STATE ROW
	TOWN ROW
<u> </u>	PERMANENT EASEMENT LINE (P)
	TEMPORARY EASEMENT LINE (T)
+	SURVEY LINE
· · · · · · · · · · · · · · · · · · ·	PROPERTY LINE (P/L)
△ SR → SR → SR →	SLOPE RIGHTS
6f ————————————————————————————————————	6F PROPERTY BOUNDARY
4f 4f	4F PROPERTY BOUNDARY
HAZ HAZ	HAZARDOUS WASTE

EPSC LAYOUT PLAN SYMBOLOGY



CONVENTIONAL TOPOGRAPHIC SYMBOLOGY



PROJECT NAME: EAST MONTPELIER VILLAGE SAFETY IMPROVEMENT PROJ. PROJECT NUMBER: STP BIKE (63)

FILE NAME: ...\CADD FILES\622472FIleg.dgn PLOT DATE: 12/12/2019 PROJECT LEADER: B.BRESLEND DESIGNED BY: P.DAY

DRAWN BY: P.DAY CHECKED BY: B. BRESLEND CONVENTIONAL SYMBOLOGY LEGEND SHEET SHEET 2 OF 44

GENERAL


- I. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAKING FIELD MEASUREMENTS OF ALL EXISTING CONDITIONS AFFECTING THE WORK. ANY DISCREPANCIES IN DIMENSIONS, CHARACTER OR EXTENT OF EXISTING FEATURES SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER BEFORE ADVANCING THE WORK. WORKING DRAWINGS REQUIRED FOR VARIOUS ITEMS OF THE WORK SHALL INDICATE THE ACTUAL FIELD MEASUREMENTS BY THE CONTRACTOR PRIOR TO SUBMITTAL FOR THE ENGINEER'S APPROVAL AND SHALL BE SO NOTED.
- 2. ITEM 201.10 "CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS" HAS BEEN INCLUDED TO REMOVE ANY VEGETATION, PARTIAL AND FULL TREE REMOVAL (INCLUDING STUMPS), THINNING AND TRIMMING FOR SIGNS, AND ANY ASSOCIATED GRUBBING WITHIN ESTABLISHED ROW. THE ENGINEER MAY EXCLUDE REMOVAL IN SOME AREAS WHERE DEEMED NECESSARY AND APPROPRIATE OR NECESSITATED BY PERMIT REQUIREMENTS.
- 3. ALL WOODY DEBRIS (TREE LIMBS, BRANCHES, ETC.) SHALL BE CHIPPED AND MULCHED ON-SITE AND USED FOR TEMPORARY EROSION CONTROL. ALL CUT TREE LOGS SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE REMOVED FROM THE SITE. ALL STUMPS SHALL BE GROUND DOWN ON SITE AND THE CHIPS USED AS EROSION CONTROL. PAYMENT FOR THE CUTTING AND DISPOSAL OF TREE LOGS, CHIPPING AND SPREADING OF WOODY DEBRIS AND GRINDING OF STUMPS SHALL BE PAID FOR UNDER ITEM 201.10, "CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS". ANY ASH TREES ENCOUNTERED MUST BE DISPOSED OF IN ACCORDANCE WITH THE "REQUIREMENTS RELATED TO EMERALD ASH BORERS" NOTICE TO BIDDERS IN THE PROJECT SPECIAL PROVISIONS.
- 4. RESTORATION OF DISTURBED AREAS: RESTORE DISTURBED AREAS, EXCEPT STONE FILL AREAS AND GRUBBING AREAS, WITH TWO INCHES TOPSOIL, SEED, FERTILIZER AND MULCH, UNLESS THE ENGINEER DIRECTS THE USE OF SUITABLE EXCAVATED MATERIAL.
- 5. ALL COMMERCIAL AND RESIDENTIAL PROPERTY OWNERS SHALL BE GIVEN 48 HOURS ADVANCE NOTIFICATION WHEN CONSTRUCTION IS TO TAKE PLACE ADJACENT TO PROPERTIES.
- 6. ALL SLOPES, PLACEMENT OF EMBANKMENT MATERIAL AND STEPPING OF LAYERS INTO OLD GROUND SHALL BE IN ACCORDANCE WITH STANDARD DRAWING B-5.
- 7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REVIEWING AND UNDERSTANDING ALL APPLICABLE ENVIRONMENTAL PERMITS AND ENSURE THAT ALL CONSTRUCTION REQUIREMENTS ARE MET.
- 8. AT COMPLETION OF GRADING, THE SLOPES, DITCHES, AND ALL DISTURBED AREAS SHALL BE SMOOTH AND FREE OF POCKETS WITH SUFFICIENT SLOPE TO ENSURE DRAINAGE.
- 9. NO WORK BEYOND THE LIMITS OF CONSTRUCTION SHOWN ON THE PLANS WILL BE ALLOWED. WORKING OUTSIDE OF THESE LIMITS MAY TRIGGER ADDITIONAL PERMITTING REQUIREMENTS, WHICH WILL BE THE CONTRACTOR'S RESPONSIBILITY.
- 10. THE CONTRACTOR SHALL SUBMIT SEDIMENT AND EROSION CONTROL METHODS TO THE ENGINEER FOR APPROVAL 14 DAYS PRIOR TO START OF WORK.
- II. TYPICAL CROSS SECTIONS ARE MEANT FOR GUIDANCE ONLY. FIELD CONDITIONS MAY VARY AND MUST BE VERIFIED BY THE CONTRACTOR.
- 12. SUPERPAVE BITUMINOUS CONCRETE PAVEMENT TOLERANCE = $+/-\frac{1}{4}$ INCH (TOTAL THICKNESS, EXCLUDING LEVELING).
- 13. SUBBASE TOLERANCE = +/-1 INCH (TOTAL THICKNESS).
- 14. THE CONTRACTOR SHALL PROVIDE A SITE-SPECIFIC EROSION PREVENTION AND SEDIMENT CONTROL PLAN IN ACCORDANCE WITH SECTION 653 OF THE STANDARD SPECIFICATIONS FOR CONSTRUCTION. ESTIMATED QUANTITIES FOR EPSC WORK HAVE BEEN INCLUDED IN THE CONTRACT FOR BIDDING PURPOSES. IF THE CONTRACTOR'S EPSC PLAN REQUIRES ITEMS OF WORK THAT ARE NOT INCLUDED IN THE PLANS IT SHALL BE PAID FOR AS PART OF ITEM 653.03 "MAINTENANCE OF EPSC PLAN".
- 15. EXISTING CONCRETE SLABS ON US ROUTE 2 ARE ASSUMED TO BE 20'-0" WIDE AND 9" THICK.

UTILITIES

- I. UTILITIES INFORMATION SHOWN HEREON WAS OBTAINED FROM THE BEST AVAILABLE SOURCES AND MAY OR MAY NOT BE EITHER ACCURATE OR COMPLETE. CONTRACTOR SHALL VERIFY THE EXACT LOCATION OF EXISTING UTILITIES AND SHALL BE RESPONSIBLE FOR ANY DAMAGE TO ANY UTILITY, PUBLIC OR PRIVATE, SHOWN OR NOT SHOWN HEREON. CONTRACTOR SHALL CONNECT OR RECONNECT ALL UTILITIES TO THE NEAREST SOURCE THROUGH COORDINATION WITH THE UTILITY OWNER.
- 2. THE CONTRACTOR SHALL NOT DISRUPT ANY EXISTING UTILITY SERVICE (PRIVATE OR PUBLIC) WITHOUT WRITTEN AUTHORIZATION FROM THE ENGINEER.
- 3. THE CONTRACTOR SHALL CONTACT "DIG SAFE" [1-888-DIG-SAFE (1-888-344-7233)] AND ALL AFFECTED UTILITY COMPANIES PRIOR TO PERFORMING ANY EXCAVATION, IN ACCORDANCE WITH DIG SAFE'S RULES OF NOTIFICATION.
- 4. ALL UTILITY POLES ARE TO REMAIN UNDISTURBED UNLESS OTHERWISE NOTED IN THESE PLANS.
- 5. SUBSURFACE FEATURES SUCH AS ELECTRIC AND TELEPHONE LINES, WATER LINES, SEWER LINES, STORM DRAIN AND CULVERTS, ETC., ENCOUNTERED IN THE CONSTRUCTION OF THE PROJECT SHALL BE PROTECTED, SUPPORTED, OR REMOVED AND REPLACED BY THE CONTRACTOR UNLESS OTHERWISE NOTED ON THE PLANS. THE COST OF THIS WORK SHALL BE INCIDENTAL TO THE CONTRACT UNLESS PAYMENT IS SPECIFICALLY NOTED AS A SEPARATE PAY ITEM. THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES AND/OR HIGHWAY MAINTENANCE DEPARTMENTS WHEN THE WORK INVOLVES THEIR RESPECTIVE FACILITIES. SEE THE UTILITIES SPECIAL PROVISIONS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.
- 6. ANY SURFACE OR SUBSURFACE FEATURES DAMAGED BY THE CONTRACTOR DURING CONSTRUCTION SHALL BE RESTORED TO A CONDITION AT LEAST EQUAL TO THAT IN WHICH THEY WERE FOUND IMMEDIATELY PRIOR TO THE BEGINNING OF CONSTRUCTION. ALL COSTS ASSOCIATED WITH THE RESTORATION SHALL BE AT THE SOLE EXPENSE OF THE CONTRACTOR.
- 7. WHEN WORKING IN THE VICINITY OF UTILITY POLES OR GUY WIRES, POLES WILL NEED TO BE SUPPORTED. THIS WORK SHALL BE COORDINATED WITH CONSOLIDATED COMMUNICATIONS. THE CONTACT SHALL BE: JOHN POMEROY (802-295-8187 OR 208-735-7029).
- 8. TOPOGRAPHICAL AND PLANIMETRIC DATE SHOWN ON THESE PLANS ARE BASED ON FIELD SURVEY COMPLETED BY DUBOIS & KING, INC. IN JULY 2014 AND PARTIALLY BY OTHERS. SINCE THAT TIME THE FOLLOWING PROJECTS HAVE BEEN CONSTRUCTED: EAST MONTPELIER NH CULV (54) AND EAST MONTPELIER BRF 037-1 (7). BASE MAPPING HAS BEEN UPDATED TO INCORPORATE THESE PROJECTS. CONTRACTOR SHALL VERIFY ALL EXISTING FEATURES PRIOR TO BIDDING ON PROJECT.

PROJECT NAME: EAST MONTPELIER VILLAGE SAFETY IMPROVEMENT PROJ.

PROJECT NUMBER: STP BIKE (63)



TYPICAL SIDEWALK SECTION WITH NEW CURB

STA. N 10+08 - STA. N 10+78 STA. N 11+46 - STA. N 12+76

CONSTRUCTION US ROUTE 2 VARIES 5′-0'' 11'-0" 4′-0'' (SEE LAYOUT SIDEWALK SHOULDER TRAVEL LANE & SECTIONS) $MILL 4'-9" (1\frac{1}{2}")$ PAY ITEM 210.10 EXISTING GRADE ∠ 4" WHITE LINE DRIVE SLOPE VARIES (SEE SECTIONS) 0.020 (MAX.) 1'-0" EX. CONCRETE SLAB ∽SAWCUT EXISTING PAVEMENT (SHALL BE CONSIDERED I' - 0'' 2" HAND-PLACED BITUMINOUS-INCIDENTAL TO PAY ITEM 210.10) CONCRETE MATERIAL . DRIVES ~9.5" SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY) ** COMMON -SEE DETAIL SHEET 2 FOR EXCAVATION TRENCH EXCAVATION OF EARTH PAY LIMITS 8" PORTLAND CEMENT -(TYP) CONCRETE SIDEWALK SUBBASE OF CRUSHED GRAVEL, FINE GRADED -PROPOSED 18" DRAINAGE

STA. N 16+09 - STA. N 16+17 (8") STA. N 16+17 - STA. QR 30+14 (5")

STA. QR 30+14 - STA. QR 30+21 (8")

STA. N 10+08 - STA. N 10+78

2" TYPE IVS WEARING COURSE SPECIAL PROVISION (BITUMINOUS 5'-0" CONCRETE PAVEMENT, SMALL QUANTITY) SIDEWALK 1'-0" l'-0" -8" PORTLAND EXISTING GRADE 7 ~2" TYPE IVS WEARING COURSE CEMENT SPECIAL PROVISION (BITUMINOUS CONCRETE CONCRETE PAVEMENT, SMALL QUANTITY) SIDEWALK -COMMON EXCAVATION

SUBBASE OF CRUSHED GRAVEL, FINE GRADED

TYPICAL SIDEWALK SECTION - POST OFFICE

9.5" BITUMINOUS CONCRETE PAVEMENT**

1.5" TYPE IVS WEARING COURSE
2" TYPE IIIS INTERMEDIATE COURSE
3" TYPE IIS BASE COURSE
3" TYPE IIS BASE COURSE


TYPICAL FLUSH SIDEWALK/DRIVEWAY SECTION


STA. N 9+94 - STA. N 10+08 STA. N 10+78 - STA. N 11+46 STA. N 12+76 - STA. N 13+59


NOT TO SCALE

PROJECT NAME: EAST MONTPELIER VILLAGE SAFETY IMPROVEMENT PROJ. PROJECT NUMBER: STP BIKE (63)

FILE NAME: ...\CADD FILES\622472FI+yp.dgn PLOT DATE: 12/12/2019
PROJECT LEADER: B. BRESLEND DRAWN BY: T. MATTHEWS
DESIGNED BY: T. MATTHEWS CHECKED BY: B. BRESLEND
TYPICAL SECTION SHEET I SHEET 4 OF 44








DESIGNED BY: T. MATTHEWS

TYPICAL SECTION SHEET 3


CHECKED BY: B. BRESLEND

SHEET 6 OF 44



PRICE FOR ITEM 406.38 "HAND-PLACED BITUMINOUS

CONCRETE MATERIAL, DRIVES".



PORTLAND CEMENT CONCRETE SIDEWALK PAD DETAIL

NOT TO SCALE


11'-0"


PORTLAND CEMENT CONCRETE PAD

SIDEWALK

NOT TO SCALE


4' -0"





SIDEWALK

4'-0''



US 2

11'-0"

NOTES:

I. THIS DETAIL IS CONFIGURED FOR AN II FOOT LANE.


SKEWED CROSSWALK PATTERN DETAIL


- 2. MARK LIGHT STRING LINE ON PAVEMENT ACROSS ROADWAY (CURB TO CURB).
- 3. ESTABLISH THE CENTER LINE OF THE ROADWAY (DOUBLE YELLOW LINE OR LANE LINE).
- 4. BLOCKS ARE PARALLEL TO THE CENTERLINE (DOUBLE YELLOW LINE OR LANE LINE).
- 5. ALWAYS START MEASURING FROM THE CENTERLINE OR LANE LINE RIGHT, WITH THE FLOW OF TRAFFIC.
- 6. PAINTED BLOCKS ARE 24 INCHES (TYPICAL).
- (*) 7. THIS DISTANCE WILL INCREASE TO 12" FOR A 12 FOOT LANE

PROJECT NAME: EAST MONTPELIER VILLAGE SAFETY IMPROVEMENT PROJ. PROJECT NUMBER: STP BIKE (63)


NOT TO SCALE

FILE NAME: ...\CADD FILES\622472FIdet.dgn PLOT DATE: 12/12/2019 PROJECT LEADER: B. BRESLEND DRAWN BY: G. CANTAVE DESIGNED BY: P.DAY CHECKED BY: B. BRESLEND DETAIL SHEET I SHEET 7 OF 44





NOTE: FLARE CURB ON UPSTREAM AND DOWNSTREAM ENDS



SECTION A-A

TREE PLANTING WELL DETAIL

NOTES:


I. EACH SUCCESSIVE COURSE OF STONE SHALL BE STAGGERED.

HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES DETAIL


	STATION	POSITION	TYPE	QUANTITY (SY)
N	10+82.	RT	PAVED	48
N	11+13.	LT	PAVED	46
N	12+92.	LT	GRAVEL	11
N	13+27.	LT	PAVED	19
N	13+53.	LT	PAVED	7
S	19+79.	RT	GRAVEL	29
S	20+38.	RT	PAVED	28
S	21+45.	RT	PAVED	33
S	22+39.	RT	GRAVEL	37
S	23+17.	RT	GRAVEL	59
		SUBTO)TAL =	317
		ROUNI	DING =	3
		ТОТ	AL =	320

PROJECT NAME: EAST MONTPELIER VILLAGE SAFETY IMPROVEMENT PROJ. PROJECT NUMBER: STP BIKE (63)

FILE NAME: ...\CADD FILES\622472FIdet.dgn PLOT DATE: 12/12/2019
PROJECT LEADER: B.BRESLEND DRAWN BY: P.DAY
DESIGNED BY: P.DAY CHECKED BY: B.BRESLEND
DETAIL SHEET 2 SHEET 8 OF 44



TRENCH DAM PLAN VIEW



SECTION B-B

STORM DRAIN

SECTION A-A

NOTES:

- I. BENTONITE TRENCH DAMS TO BE INSTALLED AROUND STORM DRAINS WHERE CONTAMINATION IS FOUND, AS DETERMINED BY THE ENGINEER, TO REDUCE PREFERENTIAL FLOW OF CONTAMINATED GROUND WATER ALONG PIPE BEDDING MATERIAL.
- 2. EXACT LOCATION, QUANTITY, SPACING, AND GEOMETRY SHALL BE AS SHOWN ON THE PLANS OR AS DETERMINED BY THE ENGINEER. PAYMENT FOR FURNISHING, INSTALLING, AND HANDLING THE BENTONITE, AND FOR ALL LABOR, TOOLS, EQUIPMENT, AND INCIDENTALS TO COMPLETE THE WORK SHALL BE CONSIDERED INCIDENTAL TO ITEMS 900.608 "SPECIAL PROVISION (EXCAVATION OF PETROLEUM CONTAMINATED SOILS, CLASS I)", 900.608 "SPECIAL PROVISION (EXCAVATION OF PETROLEUM CONTAMINATED SOILS, CLASS II)", AND 900.608 "SPECIAL PROVISION (EXCAVATION OF PETROLEUM CONTAMINATED SOILS, CLASS III)".
- 3. CONCRETE MAY BE SUBSTITUTED FOR BENTONITE AND WILL FOLLOW THE SAME GEOMETRY AS SHOWN IN THE DETAILS. IF THAT OPTION IS EXERCISED, POLYETHYLENE MATERIAL SHALL BE WRAPPED AROUND PIPING TO SEPARATE FROM CONCRETE. THE CONCRETE SHALL HAVE A MAXIMUM STRENGTH OF 125 PSI. CONCRETE, POLYETHYLENE, AND ALL MATERIALS, LABOR, EQUIPMENT, AND INCIDENTALS ASSOCIATED WITH IT SHALL BE CONSIDERED INCIDENTAL TO ITEMS 900.608 "SPECIAL PROVISION (EXCAVATION OF PETROLEUM CONTAMINATED SOILS, CLASS I)", 900.608 "SPECIAL PROVISION (EXCAVATION OF PETROLEUM CONTAMINATED SOILS, CLASS II)", AND 900.608 "SPECIAL PROVISION (EXCAVATION OF PETROLEUM CONTAMINATED SOILS, CLASS III)".

PROJECT NAME: EAST MONTPELIER VILLAGE SAFETY IMPROVEMENT PROJ. PROJECT NUMBER: STP BIKE (63)

NOT TO SCALE

FILE NAME: ...\CADD FILES\622472FIdet.dgn PLOT DATE: 12/12/2019
PROJECT LEADER: B.BRESLEND DRAWN BY: T.MATTHEWS
DESIGNED BY: B.BRESLAND CHECKED BY: -----DETAIL SHEET 3 SHEET 9 OF 44

 \bigcirc

HVCTRL

Standard Disk Stamped

Donnelly NORTH = 649672.03 EAST = 1649052.82

ELEV. =

DESCRIBED BY VERMONT AGENCY OF TRANSPORTATION 1996 (DJM)

TO REACH FROM THE NORTH INTERSECTION OF U.S.ROUTE 2 AND VT ROUTE 14 PROCEED NORTHERLY ALONG ROUTE 14 FOR 1.2 MI(1.9 KM) TO A GRAVEL DRIVE ON THE RIGHT. PROCEED UP THE GRAVEL DRIVE FOR 0.15 MI (0.24 KM) TO A PAVED DRIVE ON THE LEFT AND A YELLOW RANCH WITH A ONE CAR GARAGE. PROCEED UP THE PAVED DRIVE TO THE YELLOW RANCH. THE MARK IS 28.8 M (94.5 FT) NORTH NORTHEAST OF AN IRON PIPE SEPERATING THE TWO ADJACENT PROPERTIES, 26.5 M (86.9 FT) NORTHWEST OF THE SOUTHWEST CORNER OF THE ADJACENT WHITE RANCH, 20.2 M (66.3 FT) EAST NORTHEAST OF THE SOUTHEAST CORNER OF THE YELLOW GARAGE, AND 13.0 M (42.7 FT) EAST OF THE NORTHEAST CORNER OF THE YELLOW GARAGE.

HVCTRL

Standard Disk Stamped

Banfield

NORTH = 639661.19 EAST = 1646682.28

ELEV. =


DESCRIBED BY VERMONT AGENCY OF TRANSPORTATION 1996 (DJM)


TO REACH FROM THE JUNCTION OF U.S.ROUTE 2 AND VERMONT ROUTE 14


SOUTH IN THE VILLAGE OF EAST MONTPELIER, PROCEED SOUTH ON ROUTE 14 FOR 1.2 MI (1.9 KM) TO A DIRT ROAD ON THE LEFT. TURN LEFT ONTO DIRT ROAD AND CONTINUE FOR 0.55 MI (0.89 KM) TO A T-INTERSECTION WITH THE ROAD, TURN LEFT AT INTERSECTION (COUNTRY CLUB ROAD) AND CONTINUE FOR 0.35 MI (0.56 KM) TO A POINT WHERE THE MAIN DIRT ROAD TURNS SHARPLY RIGHT, FROM THIS POINT TURN SHARPLY LEFT ON A LESSER DIRT ROAD FOR 0.05 MI (0.08 KM) TO A DIRT DRIVE RIGHT, TURN RIGHT ONTO DRIVE, TO A TWO STORY HOUSE, AND THE SITE OF THE MARK. THE MARK IS LOCATED ON THE NORTHEAST SIDE OF THE HOUSE. THE MARK IS A STATE OF VERMONT SURVEY DISK SET IN THE TOP OF A 6X6 INCH SQUARE CONCRETE MONUMENT, FLUSH WITH THE GROUND SURFACE. IT IS LOCATED 62.5 FT (19.1 M) NORTH OF THE NORTHEAST CORNER OF HOUSE / ATTACHED GARAGE, 54 FT (16.5 M) NORTHEAST OF A QUADRUPLE WHITE BIRCH, 45.5 FT (13.9 M) NORTHWEST OF A 36 INCH OAK TREE, 17.5 FT (5.3 M) EAST OF THE SOUTHEAST CORNER OF A LARGE EXPOSED BOULDER, 10 FT (3.0 M) NORTHEAST OF THE SOUTHEAST CORNER OF A FLOWER BED, AND 0.8 FT (24.4 CM) SOUTH OF A FIBERGLASS WITNESS POST. OWNERSHIP IS MR. AND MRS. EDWARD BANFIELD. WITNESS POST. OWNERSHIP IS MR. AND MRS. EDWARD BANFIELD.


**To bring the project back to Vermont State Plane Grid Coordinates add 635,781.30 to the Northings and 1,593,715.26 to the Eastings


 \bigcirc \bigcirc \triangleleft















 \bigcirc \triangleleft









DATUM

NAVD 88 VERTICAL HORIZONTAL <u>N</u>AD 83 (92) ADJUSTMENT ____COMPASS

PROJECT NAME: EAST MONTPELIER VILLAGE SAFETY IMPROVEMENT PROJ. PROJECT NUMBER: STP BIKE (63)

FILE NAME: 622472Ftie.dqn PROJECT LEADER: B. BRESLEND DESIGNED BY: G. STOCKMAN TIE SHEET

PLOT DATE: 12/12/2019 DRAWN BY: G. STOCKMAN CHECKED BY: J. FLYNN SHEET IO OF 44

Flamout	Point	Chatian	Ni a vithi i a a	Footius	Dadina	1	Delta /Thata	Rotation		
Element	Type	Station	Northing	Easting	Radius	Length	/Theta	Direction	K	_
SW PROJECT N										
ALIGNMENT	DOD	0.00.00	644070 670	4642400.042						\dashv
Tangent	POB	9+00.00	644870.678	1643499.843						
	PC	N 14+96.22	645393.001	1643787.339					Ш	_
	lnc	N 14.0C 22	C4F2O2 001	1642707 220					П	\blacksquare
Arc	PC	N 14+96.22	645393.001	1643787.339						
	PI	N 15+10.33	645405.366	1643794.145	500	28.22	3°14'02.0"	Left		
	CC	N 15.24.44	645634.101	1643349.309						
	PT	N 15+24.44	645418.095	1643800.243					Ш	_
	рт	N 15 124 44	645419 005	1642900 242						-
Tangent	PT PC	N 15+24.44	645418.095	1643800.243						
	IPC	N 15+70.80	645459.908	1643820.272					Ш	
	РС	N 15+70.80	645459.908	1643820.272						\blacksquare
	PI		645495.483		800					
Arc	CC	N 16+10.25		1643837.313		78.83	5°38'44.6"	Right		
	PRC	N 16+49.63	645114.298 645529.21	1644541.766 1643857.772						
	IFIC	11 10+45.05	043323.21	1043637.772					Ш	_
	PRC	N 16+49.63	645529.21	1643857.772						
	PI	N 16+56.39		1643861.277						
Arc	CC	14 10130.33	645944.122	1643173.778	800	13.51	0°58'04.6"	Left		
	PCC	N 16+63.14	645540.824	1643864.683						
	11 CC	10 10 103.14	043340.024	10-300003						
	PCC	N 16+63.14	645540.824	1643864.683						
	PI	N 16+74.31	645550.466	1643870.312						
Arc	CC		645559.992	1643831.846	38.02	21.72	32°43'36.9"	Left		
	PT	N 16+84.86	645561.62	1643869.834						
	1	23.0 1100	0.3301.02					I	ш	\dashv
	РТ	N 16+84.86	645561.62	1643869.834						
Tangent	PI	N 17+36.22	645599.062	1643904.986	ł					
	I				<u> </u>			I		\neg
	PI	N 17+36.22	645599.062	1643904.986						
Tangent	POE	N 17+44.87	645607.71	1643905.13						

	1	<u> </u>				Γ		<u> </u>	\Box	_
	Point						Delta	Rotation		
Element	Type	Station	Northing	Easting	Radius	Length	/Theta	Direction	K	Р
SW PROJECT S										
ALIGNMENT										
Tangont	POB	S 19+00.00	645154.923	1643690.541						
Tangent	PI	S 21+82.50	645402.409	1643826.762						
Tangont	PI	S 21+82.50	645402.409	1643826.762						
Tangent	PC	S 22+48.03	645458.125	1643861.266						
Δ	РС	S 22+48.03	645458.126	1643861.266	1					
	PI	S 22+69.25	645476.161	1643872.435		42.42	2°56'30.6"	Diah+		
Arc	CC		645023.148	1644563.659		42.42	2 30 30.0	Right		
	PCC	S 22+90.45	645493.6	1643884.516						
	PCC	S 22+90.45	645493.6	1643884.516						
Λro	PI	S 23+34.67	645529.949	1643909.695	380	88.04	13°16'28.3"	Diah+		
Arc	CC		645277.215	1644196.889	360	00.04	15 10 20.5	Right		
	PCC	S 23+78.49	645559.545	1643942.548						
	PCC	S 23+78.49	645559.545	1643942.548						
Λro	PI	S 24+82.77	645629.342	1644020.025	204.49	200.04	27040120 511	Diaht		
Arc	CC		645333.322	1644146.344	304.48	200.94	37°48'39.5"	Right		
	PT	S 25+79.43	645636.986	1644124.025						
	•	•								_

Element	Point Type	Station	Northing	Easting	Radius	Length	Rotation Direction	K	Р
Quaker Road									
Tangent	POB	QR 30+00.00	645581.4702	1643888.47					
Tangent	POE	QR 30+75.00	645630.3546	1643831.59					

CULVERT PROJECT

EAST MONTPELIER NH CULV(54) ALIGNMENTS

	Point						Delta /	Rotation		
Element	Type	Station	Northing	Easting	Radius	Length	Theta	Direction	K	P
Tangent	POB	146+70.60	644732.1163	1643440.947						
rangent	PC	155+53.94	645506.0888	1643866.683						
	-									
	PC	155+53.94	645506.0888	1643866.683						
Arc	PI	157+62.32	645688.6765	1643967.118	300	364.27	69°34'10.93"	Right		
7 11 0	CC		645361.5001	1644129.54		004.27		Tagric		
	PT	159+18.20	645658.2945	1644173.279						
	PT	159+18.20	645658.2945	1644173.279						
Tangent	POE	159+50.95	645653.5205	1644205.673						

PROJECT NAME: EAST MONTPELIER VILLAGE SAFETY IMPROVEMENT PROJ. PROJECT NUMBER: STP BIKE (63)

FILE NAME: 622472Flalign.dgn PROJECT LEADER: B. BRESLEND DETAILS ARE NOT TO SCALE

DESIGNED BY:

B. BRESLEND

ALIGNMENT SHEET PLOT DATE: 12/12/2019 DRAWN BY: P.DAY CHECKED BY: C. LATHROP SHEET II OF 44

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIE	3		TOTALS	DESCRIPTIONS	DETAILED SUMMARY OF QUANTITIES		
ROAI	VAY ROADWAY (NO EROSION CONTROL PARTICIPATIO	FULL C. E. ITEMS	GRAND TOTAL FINAL UNIT	ITEMS	ITEM NUMBER ROUND	QUANTITIES UNIT ITEMS	
			1 LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10 -	EARTHWORKS SUMMARY	
3	0		350 CY	COMMON EXCAVATION	203.15 9	FILL REQUIRED	
2	0		240 CY	SOLID ROCK EXCAVATION	203.16 EST.	35 CY SUBTOTAL EARTHWORKS (30 CY X 1.15) FILL AVAILABLE	
9	0		950 CY	TRENCH EXCAVATION OF EARTH	204.20 8	239 CY COMMON EXCAVATION (341 CY X 0.7) 239 CY TOTAL MATERIAL AVAILABLE FOR FILL	
			10 CY	TRENCH EXCAVATION OF ROCK	204.21 -	204 CY WASTE	
			1 CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22 -		
8	5		825 CY	GRANULAR BACKFILL FOR STRUCTURES	204.30 8		
6	0		600 SY	COARSE-MILLING, BITUMINOUS PAVEMENT	210.10 51		
4	0		420 CY	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.26 7		
			10 TON	AGGREGATE SHOULDERS, RAP	402.13 4.8		
				EMULSIFIED ASPHALT	404.65 0.7		
3			320 SY	HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES	406.38 3		
7			760 LF	18" CPEP(SL)	601.2615 2		
				PRECAST REINFORCED CONCRETE DROP INLET WITH CAST IRON GRATE	604.18 -		
			4 EACH	PRECAST REINFORCED CONCRETE CATCH BASIN WITH CAST IRON GRATE	604.20 -		
				CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40 -		
				DUST CONTROL WITH WATER	609.10 EST.		
				STONE FILL, TYPE I			
8				VERTICAL GRANITE CURB	616.21 5		
4	0		490 LF	REMOVAL OF EXISTING CURB	616.41 2		
4	0		410 SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10 7		
2	0		220 SY	PORTLAND CEMENT CONCRETE SIDEWALK, 8 INCH	618.11 6		
			40 SF	DETECTABLE WARNING SURFACE	618.30 -		
			1 EACH	YIELDING MARKER POSTS	619.17 -		
	8		8 EACH	ADJUST ELEVATION OF VALVE BOX	629.20 -		
2	0		200 HR	UNIFORMED TRAFFIC OFFICERS	630.10 EST.		
	00		1200 HR	FLAGGERS	630.15 EST.		
		1	1 LS	TESTING EQUIPMENT, CONCRETE	631.16 -		
		1	1 LS	TESTING EQUIPMENT, BITUMINOUS	631.17 -		
			2 EACH	CPM SCHEDULE	633.10 -		
			1 LS	MOBILIZATION/DEMOBILIZATION	635.11 -		
			1 LS	TRAFFIC CONTROL, ALL-INCLUSIVE	641.11 -		
			4 EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15 -		
15	50		1550 LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402 20		
13	50		1350 LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412 14		
1	0		100 LF	DURABLE 8 INCH YELLOW LINE, THERMOPLASTIC	646.452 4		
			20 LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482 3		
	5		15 EACH	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492 -		
			60 LF	DURABLE CROSSWALK MARKING, THERMOPLASTIC	646.502 10		
	50		1550 LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602 20		

PROJECT NAME: EAST MONTPELIER VILLAGE SAFETY IMPROVEMENT PROJ. PROJECT NUMBER: STP BIKE (63)

FILE NAME: ...\CADD FILES\622472FIqty.dgn PLOT DATE: 12/12/2019 PROJECT LEADER: B.BRESLEND DESIGNED BY: T.MATTHEWS QUANTITY SHEET I

DRAWN BY: T. MATTHEWS CHECKED BY: C.LATHROP SHEET I2 OF 44

QUANTITY SHEET 2

SUMMARY	OF ESTIMATED QUA	ANTITIES			TOTALS DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
		ROADWAY	ROADWAY (NO FEDERAL CONTROL PARTICIPATIO	FULL C. E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER ROUND	QUANTITIES UNIT ITEMS
		1350			1350		LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612 14	SPECIAL PROVISION (BITUMINOUS CONCRETE
		300			300		SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85 13	PAVEMENT, SMALL QUANTITY)
			130		130		LB	SEED	651.15 5	60 TON WEARING COURSE TYPE IVS 55 TON INTERMEDIATE COURSE TYPE IIIS
			250		250		LB	FERTILIZER	651.18 1	150 TON BASE COURSE TYPE IIS
			3		3		TON	AGRICULTURAL LIMESTONE	651.20 0.8	5 TON ROUNDING 270 TON TOTAL
			140		140		CY	TOPSOIL	651.35 6	
			1		1		LS	EPSC PLAN	653.01 -	
			50		50		HR	MONITORING EPSC PLAN	653.02 EST.	
			1		1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	653.03 -	
			1		1		TON	HAYMULCH	653.10 -	
			40		40		CY	STABILIZED CONSTRUCTION ENTRANCE	653.35 4	
			9		9		EACH	INLET PROTECTION DEVICE, TYPE II	653.41 -	
			30		30		CY	INLET PROTECTION DEVICE, TYPE III	653.42 8	
			420		420		LF	SILT FENCE, TYPE I	653.475 2	
			550		550		LF	BARRIER FENCE	653.50 18	
		1			1		LS	TREE PROTECTION	656.85 -	
		15			15		SF	TRAFFIC SIGN, TYPE A	675.20 4.75	
		180			180		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341 -	
		21			21		EACH	REMOVING SIGNS	675.50 -	
		17			17		EACH	RESETTING SIGNS	675.60 -	
		15			15		LF	WIRED CONDUIT	678.23 3	
			10		10		CY	SPECIAL PROVISION (EXCAVATION OF PETROLEUM CONTAMINATED SOILS, CLASS	900.608 EST.	
			10		40		0)/		000,000	
			10		10		CY	SPECIAL PROVISION (EXCAVATION OF PETROLEUM CONTAMINATED SOILS, CLASS II)	900.608 EST.	
			10		10		CY	SPECIAL PROVISION (EXCAVATION OF PETROLEUM CONTAMINATED SOILS, CLASS	900.608 EST.	
		1			1		EACH	SPECIAL PROVISION (REMOVE AND RESET PEDESTRIAN SIGNAL)	900.620 -	
		1			1			SPECIAL PROVISION (REMOVE AND RESET FEDESTRIAN SIGNAL) SPECIAL PROVISION (TREE PLANTING WELL)	900.620 -	
		1			1		LU	SPECIAL PROVISION (IRCL FLANTING WELL) SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL	900.650 -	
		-						QUANTITY)(N.A.B.I.)		
		1			1		LU	SPECIAL PROVISION (MIXTURE PAYADJUSTMENT)(N.A.B.I.)	900.650 -	
		270			270		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680 5	
 									Γ	

PROJECT NAME: EAST MONTPELIER VILLAGE SAFETY IMPROVEMENT PROJ. PROJECT NUMBER: STP BIKE (63)

FILE NAME: ...\CADD FILES\622472FIqty.dgn PLOT DATE: I2/I2/20I9 PROJECT LEADER: B.BRESLEND DESIGNED BY: T.MATTHEWS QUANTITY SHEET 2

DRAWN BY: T. MATTHEWS CHECKED BY: C.LATHROP SHEET I3 OF 44

5 OF 6

RIGHT - OF - WAY DETAIL SHEET 1

				TABLE	OF PRO	OPERTY	ACQUISITION					
PARCEL NO.	PROPERTY OWNER	SHEET NO.	BEGINNING STATION	ENDING STATION	TAKE	REMAINDER	RIGH	łT		RECORDING DATA		REMARKS
1	WATSON, ROBERT R.	5 OF 6	N 09+62.79 LT	N 09+77.48 LT	AREA±	AREA±	TYPE CONSTRUCTION	(T)/(P) (T)	AREA ± 71.50	TOWN/CITY BOOK	PAGE	DELINEATE WITH BARRIER OR
	, , , , , , , , , , , , , , , , , , ,	3 31 3	N 09+62.79 LT	N 10+19.02 LT			D & C	(T)	-			GEOTEXTILE FENCE DISCONNECT & CONNECT WATER
			N 09+77.16 LT	N 09+90.87 LT			DRIVE	(T)	131.84			RECONSTRUCT DRIVE
			N 09+90.63 LT	N 10+18.99 LT			CONSTRUCTION	(T)	324.43			DELINEATE WITH BARRIER OR
			N 10+01.69 LT	N 10+19.02 LT			DETOUR	(T)	26.84			GEOTEXTILE FENCE DETOUR ROAD
2	ROLLAND, TY C. & NANCY L.	5 OF 6	N 10+01.89 LT	N 11+04.46 LT					802.01			DELINEATE WITH BARRIER OR
2	ROLLAND, 11 C. & NANC 1 L.	5 OF 6					CONSTRUCTION	(T)				GEOTEXTILE FENCE
			N 10+18.84 LT	N 11+91.79 LT			D & C	(T)	-			DISCONNECT & CONNECT WATER
			N 10+18.99 LT	N 11+63.33 LT			DETOUR	(T)	1665.87			DETOUR ROAD
			N 10+19.11 LT	N 11+02.06 LT			SLOPE	(T)	831.14			
			N 10+23.93 LT	N 10+38.91 LT			INSTALL	(T)	-			PUMP & PIPE
			N 10+37.81 LT	N 10+57.60 LT			CUL., DIT & DR	(P)	-			
			N 10+47.00 LT	-			SIGN	(P)	-			
			N 10+62.89 LT	N 10+63.08 LT			CUL., DIT & DR	(P)	-			
			N 10+92.13 LT	N 11+08.12 LT			CUL., DIT & DR	(P)	-			
			N 10+95.55 LT	N 11+25.45 LT			REMOVE & INSTALL	(T)	-			PIPE
			N 10+99.24 LT	N 11+25.32 LT			DRIVE	(T)	504.03			RECONSTRUCT DRIVE
			N 11+05.66 LT	N 11+42.63 LT			INSTALL	(T)	-			PUMP & PIPE
			N 11+22.25 LT	N 11+91.79 LT			CONSTRUCTION	(T)	1465.76			DELINEATE WITH BARRIER OR GEOTEXTILE FENCE
			N 11+22.38 LT	N 11+28.17 LT			SLOPE	(T)	31.96			
			N 11+25.17 LT	-			REMOVE	(T)	-			GUIDE POST
			N 11+42.59 LT	N 11+66.88 LT			SLOPE	(T)	11.30			
			N 11+89.00 LT	-			SIGN	(P)	-			
3	NOT USED											
4	COWAN, DANIEL F.	5 OF 6	N 11+91.79 LT	N 12+85.80 LT			CONSTRUCTION	(T)	544.81			DELINEATE WITH BARRIER OR
			N 11+91.79 LT	N 13+01.22 LT			D & C	(T)	-			GEOTEXTILE FENCE DISCONNECT & CONNECT WATER
			N 12+46.00 LT	-			SIGN	(P)	-			
			N 12+85.10 LT	N 12+99.08 LT			DRIVE	(T)	72.28			RECONSTRUCT DRIVE
			N 12+97.37 LT	N 13+01.22 LT			CONSTRUCTION	(T)	19.40			DELINEATE WITH BARRIER OR
5	BIRON, GLORIA A.,	5 OF 6	N 13+01.22 LT	N 13+64.23 LT			CONSTRUCTION	(T)	1212.55			GEOTEXTILE FENCE DELINEATE WITH BARRIER OR
	TRUSTEE OF THE GLORIA A. BIRON LIVING TRUST		N 13+01.22 LT	N 13+64.23 LT			D&C	(T)	-			GEOTEXTILE FENCE DISCONNECT & CONNECT WATER
			N 13+09.99 LT	N 13+42.38 LT			DRIVE	(T)	42.30			RECONSTRUCT DRIVE
			N 13+40.00 LT	-			SIGN	(P)	-			
			N 13+42.14 LT	N 13+47.38 LT			INSTALL	(T)	81.56			WALKWAY
			N 13+47.14 LT	N 13+59.23 LT			DRIVE	(T)	25.57			RECONSTRUCT DRIVE
					<u> </u>			<u> </u>			1	<u> </u>

REVISION	SHEET	DESCRIPTION	DATE
NO.	NO.		

TABLE OF REVISIONS

<u>LEGEND</u>

"N" US RTE 2 NORTH
"S" US RTE 2 SOUTH
"QR" QUAKER ROAD

PROJECT NAME: EAST MONTPELIER VILLAGE SAFETY IMPROVEMENT PROJECT PROJECT STP BIKE (63)

FILE NAME: 622472Fldet-row.dgn
PROJECT LEADER: B. BRESLEND
DESIGNED BY: B. BRESLEND
RIGHT OF WAY DETAIL SHEET I

PLOT DATE: 12/12/2019
DRAWN BY: O. DALMER
CHECKED BY: S. SOLLA
SHEET 14 OF 44

RIGHT - OF - WAY DETAIL SHEET 2

	TABLE OF PROPERTY ACQUISITION									
PARCEL NO.	PROPERTY OWNER	SHEET NO.	BEGINNING STATION	ENDING STATION	TAKE REMAINDER				RECORDING DATA	REMARKS
6	ROWELL, RICHARD & NANCY	5 OF 6	S 19+71.55 RT	S 19+88.38 RT	AREA± AREA±	TYPE DRIVE	(T)/(P) (T)	AREA ± 166.28	TOWN/CITY BOOK PAGE	RECONSTRUCT DRIVE
			S 19+71.55 RT	S 20+60.82 RT		D&C	(T)	-		DISCONNECT & CONNECT WATER
			S 19+85.46 RT	S 20+60.82 RT		CONSTRUCTION	(T)	441.11		DELINEATE WITH BARRIER OR
			S 19+86.17 RT	S 20+52.15 RT		SLOPE	(T)	314.55		GEOTEXTILE FENCE
			S 20+13.77 RT	-		REMOVE	(T)			TREE
			S 20+28.62 RT	-		ADJUST	(T)	-		WATER SHUT OFF VALVE BOX
			S 20+42.31 RT	S 20+60.82 RT		DRIVE	(T)	76.39		RECONSTRUCT DRIVE
7	LAMB, DURWARD D. & LINDA L.	5 OF 6	S 20+60.82 RT	S 20+78.07 RT		DRIVE	(T)	56.43		RECONSTRUCT DRIVE
			S 20+60.82 RT	S 21+57.82 RT		D&C	(T)	-		DISCONNECT & CONNECT WATER
			S 20+62.54 RT	S 21+30.62 RT		SLOPE	(T)	254.45		
			S 20+77.09 RT	-		REMOVE	(T)	-		TREE
			S 20+83.28 RT	-		INSTALL	(T)	-		TREE PLANTING WELL
			S 21+00.98 RT	-		INSTALL	(T)	-		TREE PLANTING WELL
			S 21+12.31 RT	S 21+55.81 RT		DRIVE	(T)	196.62		RECONSTRUCT DRIVE
			S 21+12.54 RT	-		INSTALL	(T)	-		TREE PLANTING WELL
			S 21+50.79 RT	S 21+57.82 RT		CONSTRUCTION	(T)	82.15		DELINEATE WITH BARRIER OR
			S 21+53.57 RT	S 21+57.82 RT		SLOPE	(T)	53.13		GEOTEXTILE FENCE
8	MOREY, ROBERT W.	5&6 OF 6	S 21+57.82 RT	S 22+27.38 RT		CONSTRUCTION	(T)	536.92		DELINEATE WITH BARRIER OR
	& GROVER-MOREY, DEBRA		S 21+57.82 RT	S 22+55.88 RT		D&C	(T)	-		GEOTEXTILE FENCE DISCONNECT & CONNECT WATER
			S 21+57.82 RT	S 22+25.23 RT		SLOPE	(T)	757.46		
			S 21+60.19 RT	-		REMOVE	(T)	-		SIGN
			S 21+61.00 RT	_		SIGN	(P)	_		
			S 22+10.89 RT	-		ADJUST	(T)	-		WATER SHUT OFF VALVE BOX
			S 22+25.10 RT	S 22+51.68 RT		DRIVE	(T)	291.63		RECONSTRUCT DRIVE
			S 22+46.03 RT	S 22+54.77 RT		SIDEWALK	(P)	3.52		LENGTH 9.18 FT
			S 22+50.95 RT	S 22+55.88 RT		CONSTRUCTION	(T)	47.95		DELINEATE WITH BARRIER OR
9	BIRON, GLORIA A.,	6 OF 6	S 22+54.68 RT	S 23+24.80 RT		SIDEWALK	(P)	74.30		GEOTEXTILE FENCE LENGTH 69.64 FT
	TRUSTEE OF THE GLORIA A. BIRON LIVING TRUST		S 22+54.68 RT	S 24+75.00 RT		D&C	(T)	-		DISCONNECT & CONNECT WATER
			S 22+54.77 RT	S 23+93.69 RT		CONSTRUCTION	(T)	422.90		DELINEATE WITH BARRIER OR
			S 22+92.58 RT	S 23+39.51 RT		DRIVE	(T)	481.32		GEOTEXTILE FENCE RECONSTRUCT DRIVE
			S 23+37.47 RT	S 24+75.00 RT		CONSTRUCTION	(T)	655.59		DELINEATE WITH BARRIER OR
										GEOTEXTILE FENCE
10	NOT USED									
					<u> </u>					

DEL VICTO		TABLE OF REVISIONS	
REVISION NO.	SHEET NO.	DESCRIPTION	DATE
			+
			+
	 		1

<u>LEGEND</u>

"N" US RTE 2 NORTH
"S" US RTE 2 SOUTH
"QR" QUAKER ROAD

PROJECT NAME: EAST MONTPELIER VILLAGE SAFETY IMPROVEMENT PROJECT PROJECT NUMBER: STP BIKE (63)

FILE NAME: 622472Fldet-row.dgn
PROJECT LEADER: B. BRESLEND
DESIGNED BY: B. BRESLEND
RIGHT OF WAY DETAIL SHEET 2

PLOT DATE: 12/12/2019
DRAWN BY: O. DALMER
CHECKED BY: S. SOLLA
SHEET 15 OF 44

RIGHT - OF - WAY DETAIL SHEET 3

TABLE OF PROPERTY ACQUISITION													
PARCEL NO.	PROPERTY OWNER	SHEET NO.	BEGINNING STATION	ENDING STATION	TAKE	REMAINDER	RIGH	IT		RECORDING	B DATA		REMARKS
11	FIRSTLIGHT	5&6 OF 6	N 09+48.20 LT	S 24+75.00 RT	AREA±	AREA±	TYPE	(T)/(P)	AREA ±	TOWN / CITY	ВООК	PAGE	INTERNET
12	GREEN MOUNTAIN POWER	5&6 OF 6	N 09+48.20 LT	S 24+75.00 RT									ELECTRIC
13	FAIRPOINT COMMUNICATIONS	5&6 OF 6	N 09+48.20 LT	S 24+75.00 RT									TELEPHONE
14	COMCAST CORPORATION	5&6 OF 6	N 09+48.20 LT	S 24+75.00 RT									CABLE
15	CRYSTAL SPRINGS WATER COMPANY, INC.	5&6 OF 6	N 09+48.20 LT	S 24+75.00 RT									WATER
_													
				1								<u> </u>	

1	

TABLE OF REVISIONS

DESCRIPTION

DATE

REVISION SHEET


<u>LEGEND</u>


"N" US RTE 2 NORTH
"S" US RTE 2 SOUTH
"QR" QUAKER ROAD


PROJECT NAME: EAST MONTPELIER VILLAGE SAFETY IMPROVEMENT PROJECT PROJECT NUMBER: STP BIKE (63)


FILE NAME: 622472Fldet-row.dgn
PROJECT LEADER: B. BRESLEND
DESIGNED BY: B. BRESLEND
RIGHT OF WAY DETAIL SHEET 3


PLOT DATE: 12/12/2019
DRAWN BY: O. DALMER
CHECKED BY: S. SOLLA
SHEET 16 OF 44














EPSC PLAN NARRATIVE

1.1 PROJECT DESCRIPTION

THIS PROJECT IS LOCATED IN THE COUNTY OF WASHINGTON, TOWN OF EAST MONTPELIER, AT THE INTERSECTION OF US ROUTE 2 AND QUAKER ROAD AND US ROUTE 2 AND VT ROUTE 14. THE PROJECT IS 927 FEET IN LENGTH, BEGINNING ON THE SOUTH WEST OF US ROUTE 2 AND CONTINUING NORTH EAST TO MEET VT ROUTE 14. PROJECT INCLUDES PORTLAND CEMENT CONCRETE SIDEWALKS, VERTICAL GRANITE CURBING, PAVEMENT STRIPING, GRADING, SIGNING, DRAINAGE MODIFICATIONS, AND OTHER HIGHWAY RELATED ITEMS.

NOTE: AREA OF DISTURBANCE INCLUDES LIMITS OF EARTH DISTURBANCE WITHIN THE PROJECT AREA, AS WELL AS WASTE, BORROW AND STAGING AREAS, AND OTHER EARTH DISTURBING ACTIVITIES WITHIN OR DIRECTLY ADJACENT TO THE PROJECT LIMITS AS SHOWN ON THE ATTACHED EPSC PLAN. TOTAL AREA OF DISTURBANCE AS SHOWN ON THE ATTACHED EPSC PLAN IS APPROXIMATELY 0.45 ACRES.

IT IS ANTICIPATED THAT THIS PROJECT WILL LAST ONE CONSTRUCTION SEASON.

1.2 SITE INVENTORY

1.2.1 TOPOGRAPHY

THE TOPOGRAPHY OF THE AREA CONSISTS MOSTLY OF FLAT EMBANKMENTS WITH STEEPER PARTS AT THE STREAM AREA AND AT THE NORTH EAST OF THE PROJECT AREA. IT IS MOSTLY RESIDENTIAL AND SMALL BUSINESS AREA. THE FARMLAND IS LOCATED TO THE EAST OF THE PROJECT.

1.2.2 DRAINAGE, WATERWAYS, BODIES OF WATER, AND PROXIMITY TO NATURAL OR MAN-MADE WATER FEATURES

WINOOSKI RIVER TAKES PLACE AT THE SOUTH OF THE PROJECT AND NOT WITHIN PROJECT AREA.

THERE IS A CROSS CULVERT AT THE SOUTH WEST PROJECT AREA THAT COLLECTS RUNOFF WATER FROM THE ROADWAY AND ADJACENT SLOPES AND EVENTUALLY FEEDS INTO THESE WATER SOURCES.

1.2.3 VEGETATION

THE VEGETATION IN THE PROJECT AREA CONSISTS PRIMARILY OF RESIDENTIAL AND SMALL BUSINESS LAWNS AND SHADE TREES.

THE IMPACT TO VEGETATION WILL BE LIMITED TO THAT WHICH IS DIRECTLY AFFECTED BY ANY SLOPE STABILIZATION ALONG THE PROJECT. DISTURBED VEGETATION WILL BE REESTABLISHED WITH STANDARD SEED AND MULCH PRACTICES.

1.2.4 **SOILS**

ALL SOIL DATA CAME FROM THE U.S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE FOR THE COUNTY OF FRANKLIN, VERMONT. SOILS ON THE PROJECT SITE ARE:

ADAMS LOAMY FINE SAND, 0-3 % SLOPES, HYDROLOGIC SOIL GROUP: A, K FACTOR = 0.15

DUMMERSTON FINE SANDY LOAM. 15-25% SLOPES, HYDROLOGIC SOIL GROUP: B, K FACTOR = 0.28

CABOT SOIL LOAM, 0-3% SLOPES, HYDROLOGIC SOIL GROUP:D, K FACTOR = 0.43

THE SOILS WITHIN THIS PROJECT ARE CONSIDERED MODERATE TO HIGHLY ERODIBLE DUE TO THE "K FACTOR".

NOTE: K-VALUES GENERALLY INDICATE THE FOLLOWING: 0.0-0.23 = LOW EROSION POTENTIAL 0.24-0.36 = MODERATE EROSION POTENTIAL 0.37 AND HIGHER = HIGH EROSION POTENTIAL

1.2.5 SENSITIVE RESOURCE AREAS

CRITICAL HABITATS: NO HISTORICAL OR ARCHEOLOGICAL AREAS: NO PRIME AGRICULTURAL LAND: YES

THREATENED AND ENDANGERED SPECIES: THE VERMONT AGENCY OF NATURAL RESOURCES ATLAS MAPPING SHOWS NO RARE, THREATENED OR ENDANGERED SPECIES OR SIGNIFICANT NATURAL COMMUNITIES WITHIN THE PROJECT AREA, AND NONE WERE OBSERVED DURING TWO FIELD REVIEWS.

HABITAT TREES HAVE BEEN IDENTIFIED INSIDE THE PROJECT LIMITS AND THE PROJECT IS SUBJECT TO RESTRICTIONS. THE CONTRACTOR SHALL NOT CUT TREES GREATER THAN THREE INCHES IN DIAMETER FROM APRIL 15TH THROUGH OCTOBER 31. THE CONTRACTOR SHALL SCHEDULE THE REMOVAL OF TREES GREATER THAN THREE INCHES IN DIAMETER OUTSIDE OF THE RESTRICTED TIME. SHOULD THE CONTRACTOR PROPOSE TO CUT TREES WITHIN THE RESTRICTED TIMEFRAME THEY MUST FIRST HIRE A QUALIFIED BIOLOGIST TO CONDUCT A SUITABLE HABITAT ASSESSMENT AND ACOUSTIC MONITORING AS NECCESSARY. A REPORT SHALL BE SUBMITTED TO THE VTRANS BIOLOGIST FOR REVIEW. NO CUTTING IN THE RESTRICTED TIMEFRAME SHALL OCCUR UNTIL PERMISSION IS GRANTED BY THE VTRANS ENVIRONMENTAL SECTION.

WATER RESOURCE: NO

WETLANDS: TWO CLASS III WETLANDS LOCATED AT THE SOUTH WEST OF THE PROJECT.

1.3 RISK EVALUATION

THIS PROJECT DOES NOT FALL UNDER THE JURISDICTION OF GENERAL PERMIT 3-9020 FOR STORMWATER RUNOFF FROM CONSTRUCTION SITES. SHOULD CHANGES PRIOR TO OR DURING CONSTRUCTION RESULT IN ONE OR MORE ACRES OF EARTH DISTURBANCE OR SHOULD THE PROJECT BECOME PART OF A LARGER PLAN OF DEVELOPMENT, THE CONTRACTOR WILL BE RESPONSIBLE FOR ANY ADDITIONAL PERMITTING.

1.4 EROSION PREVENTION AND SEDIMENT CONTROL

THE EROSION CONTROL PLANS ARE MEANT AS A GUIDELINE FOR PREVENTING EROSION AND CONTROLLING SEDIMENT TRANSPORT. THE PRINCIPLES OUTLINED IN THIS NARRATIVE CONSIST OF APPLYING MEASURES THROUGHOUT CONSTRUCTION OF THE PROJECT IN ORDER TO MINIMIZE SEDIMENT TRANSPORT TO THE RECEIVING WATERS. THE MEASURES INCLUDE STABILIZATION AND STRUCTURAL PRACTICES, STORM WATER CONTROLS AND OTHER POLLLUTION PREVENTION PRACTICES. THEY HAVE BEEN PROPOSED BY THE DESIGNER AS A BASIS FOR PROTECTING RESOURCES AND WILL NEED TO BE BUILT UPON BASED ON THE SPECIFC MEANS AND METHODS OF THE CONTRACTOR. REFER TO THE LOW RISK SITE HANDBOOK AND APPROPRIATE DETAIL SHEETS FOR SPECIFIC GUIDANCE AND CONSTRUCTION DETAILING.

ALL MEASURES SHALL BE REGULARLY MAINTAINED AND SHALL BE CHECKED FOR SEDIMENT BUILD-UP. SEDIMENT SHALL BE DISPOSED OF AT AN APPPROVED SITE WHERE IT WILL NOT BE SUBJECT TO EROSION.

1.4.1 MARK SITE BOUNDARIES

SITE BOUNDARIES AND AREAS CONSTRUCTION EQUIPMENT CAN ACCESS SHALL BE DELINEATED.

BARRIER FENCING (BF) AND SILT FENCING SHALL BE USED TO PHYSICALLY MARK SITE BOUNDARIES.

1.4.2 LIMIT DISTURBANCE AREA

PREVENTING INITIAL SOIL EROSION BY MINIMIZING THE EXPOSED AREA IS MUCH MORE EFFECTIVE THAN TREATING ERODED SEDIMENT. EARTH DISTURBANCE CAN BE MINIMIZED THROUGH CONSTRUCTION PHASING BY ONLY OPENING UP EARTH AS NECESSARY. THIS CAN LIMIT THE AREA THAT WILL BE DISTURBED AND EXPOSED TO EROSION. EMPLOY TEMPORARY CONSTRUCTION STABILIZATION PRACTICES IN INCREMENTAL STAGES AS PHASES CHANGE. FOR PROJECTS WHICH FALL UNDER THE CONSTRUCTION GENERAL PERMIT, ONLY THE ACREAGE LISTED ON THE PERMIT AUTHORIZATION MAY BE EXPOSED AT ANY GIVEN TIME.

MAINTAINING VEGETATED BUFFERS ALONG STREAM BANKS, WETLANDS OR OTHER SENSITIVE AREAS IS A CRUCIAL EROSION AND SEDIMENT CONTROL MEASURE THAT SHOULD BE ESTABLISHED WHEREVER POSSIBLE.

1.4.3 SITE ENTRANCE/EXIT STABILIZATION

TRACKING OF SEDIMENT ONTO PUBLIC HIGHWAYS SHALL BE MINIMIZED TO REDUCE THE POTENTIAL FOR RUNOFF ENTERING RECEIVING WATERS. INSTALLATION SHALL COINCIDE WITH THE CONTRACTORS. PROGRESS SCHEDULE. STABILIZED CONSTRUCTION ENTRANCES SHALL BE INSTALLED AS PROPOSED ON THE EPSC PLAN AND ANYWHERE EQUIPMENT WILL BE GOING FROM AREAS OF EXPOSED SOILS TO PAVED SURFACES.

1.4.4 INSTALL SEDIMENT BARRIERS

SEDIMENT BARRIERS SHALL BE UTILIZED TO INTERCEPT RUNOFF AND ALLOW SUSPENDED SEDIMENT TO SETTLE OUT. THEY SHALL BE INSTALLED PRIOR TO ANY UP SLOPE WORK.

SILT FENCE WILL BE INSTALLED AS PROPOSED ON THE EPSC PLAN.

1.4.5 DIVERT UPLAND RUNOFF

DIVERSIONARY MEASURES SHALL BE USED TO INTERCEPT RUNOFF FROM ABOVE THE CONSTRUCTION AND DIRECT IT AROUND THE DISTURBED AREA SO THAT CLEAN WATER DOES NOT BECOME MUDDIED WHILE TRAVELING OVER EXPOSED SOILS ON THE CONSTRUCITON SITE.

THE PROJECT AREA IS RELATIVELY FLAT. THEREFORE IT IS NOT ANTICIPATED THAT DIVERSION MEASURES. WILL BE NECESSARY.

1.4.6 SLOW DOWN CHANNELIZED RUNOFF

NO CHECK STRUCTURES

1.4.7 CONSTRUCT PERMANENT CONTROLS

PERMANENT STORM WATER TREATMENT DEVICES SHALL BE INSTALLED AS SHOWN ON THE PLANS AND IN ACCORDANCE WITH PERMIT CONDITIONS.

1.4.8 STABILIZE EXPOSED SOILS DURING CONSTRUCTION

ALL AREAS OF DISTURBANCE MUST HAVE TEMPORARY STABILIZATION IN PLACE WITHIN 48 HOURS OF DISTURBANCE OR IN ACCORDANCE WITH THE CONSTRUCTION GENERAL PERMIT 3-9020 AUTHORIZATION.

SURFACE ROUGHENING OF ALL EXPOSED SLOPES, COMBINED WITH TEMPORARY MULCHING, SHALL BE UTILIZED ON A REGULAR BASIS.

DISTURBED AREAS AND SOIL STOCKPILES THAT WILL NOT BE WORKED ON FOR MORE THAN 7 DAYS SHALL BE TEMPORARY STABILIZED WITH MULCH/RECP WITHIN 48 HOURS. EXPOSED AREAS THAT HAVE ACHIEVED FINAL GRADAE SHALL BE PERMANENTLY STABILIZED WITHIN 48 HOURS.

SOIL AT FINAL GRADE

EXPOSED SOIL MUST BE STABILIZED WITHIN 48 HOURS OF REACHING FINAL GRADE.

SEED. MULCH. FERTILIZER AND LIME SHALL BE USED TO ESTABLISH PERMANENT VEGETATION.

1.4.11 DE-WATERING ACTIVITIES

DISCHARGE FROM DEWATERING ACTIVITIES THAT FLOWS OFF OF THE CONSTRUCTION SITE MUST NOT CAUSE OR CONTRIBUTE TO A VIOLATION OF THE VERMONT WATER OUALITY STANDARDS.

1.4.12 INSPECT YOUR SITE

INSPECT THE PROJECT SITE BASED ON SPECIAL PROVISION REQUIREMENTS OR CONSTRUCTION GENERAL PERMIT AUTHORIZATION STIPULATIONS.

1.5 SEQUENCE AND STAGING

THIS SECTION WILL BE DEVELOPED BY THE CONTRACTOR USING THE GUIDANCE OUTLINED IN THE VTRANS EPSC PLAN CONTRACTOR CHECKLIST.

1.5.1 CONSTRUCTION SEQUENCE

1.5.2 OFF-SITE ACTIVITIES

IN ADDITION TO THE CONTRACTOR CHECKLIST ANY ACTIVITIES OUTSIDE THE CONSTRUCTION LIMITS SHALL FOLLOW SPECIFICATION 105.25- 105.29 OF THE STANDARD SPECIFICATIONS FOR CONSTRUCTION.


1.5.3 UPDATES

PROJECT NAME: EAST MONTPELIER VILLAGE SAFTEY IMPROVEMENT PROJ. PROJECT NUMBER: STP BIKE (63)

FILE NAME: z12c414EPSC_Narrative.dqn PLOT DATE: 12/12/2019 PROJECT LEADER: B. BRESLEND DESIGNED BY: B. BRESLEND

EPSC NARRATIVE


DRAWN BY: O. DALMER CHECKED BY: C. LATHROP SHEET 23 OF 44



ADAPTED FROM DETAILS PROVIDED BY: NEW YORK STATE

DEC ORIGINALLY DEVELOPED BY USDA-NRCS

VERMONT DEPARTMENT OF ENVIRONMENTAL CONSERVATION



STANDARD SYMBOLS

SILT FENCE (LINE STYLE) 649.51, DETAIL - X - X -SILT FENCE WOVEN WIRE (LINE STYLE) 649.515, DETAIL STABILIZED CONSTRUCTION ENTRANCE 653.35, DETAIL, VEHICLE TRACKING PAD STONE & BLOCK DROP INLET PROTECTION 653.40, DETAIL SURFACE ROUGHENING INCIDENTAL TO CONTRACT TURBIDITY CURTAIN 649.61, DETAIL, FILTER CURTAIN 653.20, TEMPORARY EROSION MATTING 651.20, AGRICULTURAL LIMESTONE 651.18, FERTILAZER 651.15, SEED ADAPTED FROM DETAILS PROVIDED BY: NEW YORK STATE STANDARD SYMBOLS

DEC ORIGINALLY DEVELOPED BY USDA-NRCS

VERMONT DEPARTMENT OF ENVIRONMENTAL CONSERVATION





- 1. THESE PLANS SHOW A CONCEPTUAL EROSION CONTROL PLAN. THE CONTRACTOR MUST SUBMIT A EROSION PREVENTION AND SEDIMENT CONTROL PLAN FOR APPROVAL.
- 2. TEMPORARY EROSION CONTROL MEASURES ARE CONCEPTUALLY SHOWN. THE CONTRACTOR MAY RELOCATE TEMPORARY MEASURES TO IMPROVE EROSION CONTROL WITH APPROVAL OF THE ENGINEER AND ON SITE COORDINATOR. SILT FENCE SHALL NOT BE INSTALLED ACROSS CONTOURS.
- 3. THE CONTRACTOR SHALL USE OTHER TEMPORARY EROSION CONTROL MEASURES AS NECESSITATED BY THE SEQUENCE OF CONSTRUCTION OR AS DIRECTED BY THE ENGINEER AND ON SITE COORDINATOR.
- 4. REFER TO TEMPORARY EROSION CONTROL DETAIL SHEETS FOR ADDITIONAL DETAILS.


PROJECT NAME: EAST MONTPELIER VILLAGE SAFTEY IMPROVEMENT PROJ. PROJECT NUMBER: STP BIKE (63)


FILE NAME: z12c414EPSC_Narrative.dgn PLOT DATE: 12/12/2019 PROJECT LEADER: B. BRESLEND DESIGNED BY: B. BRESLEND EPSC LEGEND & NOTES


DRAWN BY: O. DALMER CHECKED BY: C. LATHROP SHEET 24 OF 44














	VAOT LOW GROW/FINE FESCUE MIX									
	LBS/AC									
WEIGHT	BROADCAST	HYDROSEED	NAME	LATIN NAME	GERM	PURITY				
38%	57	95	CREEPING RED FESCUE	FESTUCA RUBRA VAR. RUBRA	90%	98%				
29%	43.5	72.5	HARD FESCUE	FESTUCA LONGIFOLIA	85%	95%				
15%	22.5	37.5	CHEWINGS FESCUE	FESTUCA RUBRA VAR. COMMUTATA	87%	95%				
15%	22.5	37.5	ANNUAL RYEGRASS	LOLIUM MULTIFLORUM	90%	95%				
3%	4.5	7.5	INERTS							
100%	150	250								


	VAOT RURAL AREA MIX									
	LBS/AC									
WEIGHT	BROADCAST	HYDROSEED	NAME	LATIN NAME	GERM	PURITY				
37.5%	22.5	45	CREEPING RED FESCUE	FESTUCA RUBRA VAR. RUBRA	85%	98%				
37.5%	22.5	45	TALL FESCUE	FESTUCA ARUNDINACEA	90%	95%				
5.0%	3	6	RED TOP	AGROSTIS GIGANTEA	90%	95%				
15.0%	9	18	WHITE FIELD CLOVER	TRIFOLIUM REPENS	85%	98%				
5.0%	3	6	ANNUAL RYE GRASS	LOLIUM MULTIFLORUM	85%	95%				
100%	60	120								

GENERAL AMENDMENT GUIDANCE								
FERTILIZER	LIME							
10/20/10	AG LIME	PELLITIZED						
500 LBS/AC	2 TONS/AC	1 TONS/AC						

CONSTRUCTION GUIDANCE

- I.SEED MIX: THE CONTRACTOR SHALL COORDINATE WITH THE RESIDENT ENGINEER ON WHICH SEED MIX TO USE.
- 2. SEED MIX: USE AS INDICATED IN THE PLANS AND/OR FOR ALL ESTABLISHED UPLAND (NON WETLAND) AREAS DISTURBED BY THE CONTRACTOR.
- 3.ALL SEED MIXTURES: SHALL NOT HAVE A WEED CONTENT EXCEEDING 0.40% BY WEIGHT AND SHALL BE FREE OF ALL NOXIOUS SEED.
- 4.FERTILIZER AND LIMESTONE: SHALL FOLLOW RATES SHOWN ON PLAN OR AS DIRECTED BY THE ENGINEER.
- 5.HAY MULCH: TO BE PLACED ON EARTH SLOPES AT THE RATE OF 2 TONS/ACRE, ACHIEVE 90% GROUND COVER OR AS DIRECTED BY THE ENGINEER.
- 6. HYDROSEEDING: ALTHOUGH GUIDANCE IS GIVEN ABOVE THE SITE CONDITIONS AND THE TYPE OF HYDROSEED PROPOSED FOR USE WILL ULTIMATELY DICTATE THE AMOUNTS AND TYPES OF SOIL AMENDMENTS TO BE APPLIED.
- 7. TURF ESTABLISHMENT: PLACING SEED, FERTILIZER, LIME AND MULCH PRIOR TO SEPTEMBER 15 AND AFTER APRIL 15 CAN BETTER ENSURE A VIGOROUS GROWTH OF GRASS.

ADAPTED FROM VTRANS TECHNICAL LANDSCAPE MANUAL FOR ROADWAYS AND TRANSPORTATION FACILITIES	TURF ESTABLISHMENT
THIS WORK SHALL BE PERFORMED IN ACCORDANCE WITH SECTION 651 FOR SEED (PAY ITEM 651.15)	REVISIONS JANUARY 12, 2015 WHF



CONSTRUCTION SPECIFICATIONS

- I.STONE SIZE- USE 1-4" STONE, RECLAIMED OR RECYCLED CONCRETE EQUIVALENT.
- 2.LENGTH- NOT LESS THAN 50' (EXCEPT ON A SINGLE RESIDENCE LOT WHERE A 30' MINIMUM LENGTH APPLIES).
- 3. THICKNESS- NOT LESS THAN 8".
- 4. WIDTH- 12' MINIMUM, BUT NOT LESS THAN THE FULL WIDTH AT POINTS WHERE INGRESS OR EGRESS OCCURS. 24' IF SINGLE ENTRANCE TO SITE.
- 5. GEOTEXTILE MUST BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING STONE.
- 6.SURFACE WATER- ALL SURFACE WATER FLOWING OR DIVERTED TOWARD CONSTRUCTION ENTRANCES SHALL BE PIPED BENEATH THE ENTRANCE. IF PIPING IS IMPRACTICAL. A MOUNTABLE BERM WITH 5: I SLOPES WILL BE PERMITTED.
- 7. MAINTENANCE THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY, ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY MUST BE REMOVED IMMEDIATELY.
- 8. WHEN WASHING IS REQUIRED. IT SHALL BE DONE ON AN AREA STABILIZED WITH STONE AND WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE.
- 9. PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED ACCORDING TO PERMIT REQUIREMENTS.


ADAPTED FROM DETAILS PROVIDED BY: NEW YORK STATE DEC ORIGINALLY DEVELOPED BY USDA-NRCS VERMONT DEPARTMENT OF ENVIRONMENTAL CONSERVATION


STABILIZED CONSTRUCTION ENTRANCE

NOTES:

REFER TO "THE VERMONT STANDARDS & SPECIFICATIONS FOR EROSION PREVENTION & SEDIMENT CONTROL -2006- "FROM THE VT AGENCY OF NATURAL RESOURCES FOR ADDITIONAL GUIDANCE.

THIS WORK SHALL BE PERFORMED IN ACCORDANCE WITH SECTION 653 FOR VEHICLE TRACKING PAD (PAY ITEM 653.35) OR AS SPECIFIED IN THE CONTRACT.





- . WOVEN WIRE REINFORCED FENCE IS REQUIRED WITHIN 100' UPSLOPE OF RECEIVING WATERS WHEN THE PROJECT FALLS UNDER A CONSTRUCTION STORMWATER PERMIT. WOVEN WIRE SHALL BE A MIN. 14 GAUGE WITH A 6" MAX. MESH OPENING.
- 2. FILTER CLOTH SHALL BE EITHER FILTER X, MIRAFIIOOX, STABILINKA TI4ON OR APPROVED EQUIVALENT.
- 3. POST SPACING FOR WIRE-BACKED FENCE SHALL BE 10' MAXIMUM. FOR FILTER-CLOTH FENCE, WHEN ELONGATION IS >50%, POST SPACING SHALL NOT EXCEED 4' AND WHEN ELONGATION IS <50%. POST SPACING SHALL NOT EXCEED
- 4.WOVEN WIRE FENCE IS TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES. FILTER CLOTH IS TO BE FASTENED SECURELY TO WOVEN WIRE FENCE WITH TIES SPACED EVERY 24" AT TOP AND MID SECTION.
- 5. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER THEY SHALL BE OVER-LAPPED BY 6" AND FOLDED.
- 6. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN SEDIMENT REACHES HALF OF FABRIC HEIGHT.

ADAPTED FROM DETAILS PROVIDED BY: NEW YORK STATE DEC ORIGINALLY DEVELOPED BY USDA-NRCS VERMONT DEPARTMENT OF ENVIRONMENTAL CONSERVATION

GUIDANCE.

SILT FENCE

REFER TO "THE VERMONT STANDARDS & SPECIFICATIONS FOR EROSION PREVENTION & SEDIMENT CONTROL -2006- "FROM THE VT AGENCY OF NATURAL RESOURCES FOR ADDITIONAL


THIS WORK SHALL BE PERFORMED IN ACCORDANCE WITH SECTION 649 AND AS SHOWN IN THE PLANS FOR GEOTEXTILE FOR SILT FENCE (PAY ITEM 649.51) OR GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED (PAY ITEM 649.515).

REVISIONS MARCH 21, 2008 WHF DECEMBER II. 2008 WHF JANUARY 13.2009 WHF

PROJECT NAME: EAST MONTPELIER VILLAGE SAFTEY IMPROVEMENT PROJ. PROJECT NUMBER: STP BIKE (63)

FILE NAME: z12c414EPSC_Narrative.dqn PLOT DATE: 12/12/2019 PROJECT LEADER: B. BRESLEND DESIGNED BY: B. BRESLEND EPSC DETAILS SHEET I

DRAWN BY: O. DALMER CHECKED BY: C. LATHROP SHEET 31 OF 44



CONSTRUCTION SPECIFICATIONS

- I.FILTER FABRIC SHALL HAVE AN APPARENT OPENING SIZE OF 40-85. BURLAP MAY BE USED FOR SHORT TERM APPLICATIONS.
- 2. CUT FABRIC FROM A CONTINUOUS ROLL TO ELIMINATE JOINTS. IF JOINTS ARE NEEDED THEY WILL BE OVERLAPPED TO THE NEXT STAKE.
- 3. STAKE MATERIALS WILL BE STANDARD 2"x 4" WOOD OR EQUIVALENT METAL WITH A MINIMUM LENGTH OF 3'.
- 4.SPACE STAKES EVENLY AROUND INLET 3' APART AND DRIVE A MINIMUM 18" DEEP. SPANS GREATER THAN 3' MAY BE BRIDGED WITH THE USE OF WIRE MESH BEHIND THE FILTER FABRIC FOR SUPPORT.
- 5. FABRIC SHALL BE EMBEDDED I' MINIMUM BELOW GROUND AND BACKFILLED. IT SHALL BE SECURELY FASTENED TO THE STAKES AND FRAME.
- 6. A 2" × 4" WOOD FRAME SHALL BE COMPLETED AROUND THE CREST OF THE FABRIC FOR OVER FLOW STABILITY.
- 7. MAXIMUM DRAINAGE AREA I ACRE

ADAPTED FROM DETAILS PROVIDED BY: NEW YORK STATE DEC ORIGINALLY DEVELOPED BY USDA-NRCS VERMONT DEPARTMENT OF ENVIRONMENTAL CONSERVATION


FILTER FABRIC DROP INLET PROTECTION

NOTES:

REFER TO "THE VERMONT STANDARDS & SPECIFICATIONS FOR EROSION PREVENTION & SEDIMENT CONTROL -2006- "FROM THE VT AGENCY OF NATURAL RESOURCES FOR ADDITIONAL GUIDANCE.

THIS WORK SHALL BE PERFORMED IN ACCORDANCE WITH SECTION 653 FOR INLET PROTECTION DEVICE, TYPE I (PAY ITEM 653.40).

REVISIONS	
MARCH 7,2008	WHF
IANUARY 13, 2009	WHF



- I.USE 2" TO 3" STONE. FILTERING STONE SHALL BE 3/4".
- 2. PLACE STONE OVER GEOTEXTILE.
- 3. ONCE THE AREAS UPSTREAM FROM THE CHECK DAM ARE STABILIZED WITH VEGETATION, THE SEDIMENT TRAPPED BEHIND THE DAM SHALL BE DISPOSED OF IN AN APPRÓVED WASTE AREA.
- 4. THE CHECK DAM(S) SHALL BE FLATTENED AND GRADED IN A MANNER WHICH PROTECTS THE AREA FROM EROSION AND CHANNEL BLOCKAGE . (GEOTEXTILE MUST BE REMOVED).
- 5. THE GEOTEXTILE MUST BE DISPOSED OF APPROPRIATELY.
- 6. THE AREA CONTRIBUTING TO THE CHECK DAM SHALL NOT EXCEED 4 ACRES.

ADAPTED FROM DETAILS PROVIDED BY: ILLINOIS USDA-NRCS ORIGINALLY DEVELOPED BY USDA-NRCS

PIPE INLET PROTECTION

REVISIONS MARCH 6, 2008 JANUARY 13, 2009

WHF


WHF

THIS WORK SHALL BE PERFORMED IN ACCORDANCE WITH SECTION 653 FOR INLET PROTECTION DEVICE, TYPE I (PAY ITEM 653.40).

> PROJECT NAME: EAST MONTPELIER VILLAGE SAFTEY IMPROVEMENT PROJ. PROJECT NUMBER: STP BIKE (63)

FILE NAME: 622472FIEPSC_Narrative.dqn PLOT DATE: 12/12/2019 PROJECT LEADER: B. BRESLEND DESIGNED BY: B. BRESLEND EPSC DETAILS SHEET 2

DRAWN BY: O. DALMER CHECKED BY: C. LATHROP SHEET 32 OF 44



VERMONT DEPARTMENT OF ENVIRONMENTAL CONSERVATION

NOTES:

REFER TO "THE VERMONT STANDARDS & SPECIFICATIONS FOR EROSION PREVENTION & SEDIMENT CONTROL -2006- "FROM THE VT AGENCY OF NATURAL RESOURCES FOR ADDITIONAL GUIDANCE.

THIS WORK SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT

REVISIONS	
APRIL I, 2008	WHF
JANUARY 13, 2009	WHF

PROJECT NAME: EAST MONTPELIER VILLAGE SAFTEY IMPROVEMENT PROJ. PROJECT NUMBER: STP BIKE (63)

FILE NAME: 622472FIEPSC_Narrative.dgn PLOT DATE: 12/12/2019 PROJECT LEADER: B. BRESLEND DESIGNED BY: B. BRESLEND EPSC DETAILS SHEET 3

DRAWN BY: O. DALMER CHECKED BY: C. LATHROP SHEET 33 OF 44

STATE OF VERMONT TRAFFIC SIGN SUMMARY SHEET 1 AGENCY OF TRANSPORTATION EXIST POST NO. FLANGED CHANNEL SIGN DIMENSIONS **NEW & RESETTED SIGNS** SIGN DETAIL TUBULAR STEEL SQUARE STEEL (in) W-SHAPE STEEL **MILE MARKER** 1.75 2.00 2.50 3.00 4.00 4.0 MOD 3.00 3.50 4.00 5.00 FTG. SIZE STATION OR REMARKS DETAIL ON STANDARD RES (LB / FT) SIGN NUMBER "B" 24" 30" WIDTH | HEIGHT "A" SHEET SIGN TIS NUMBER NUMBER 1.12 | 2.00 | 3.00 | 1.88 | 2.42 | 3.35 1.30 | 1.70 | 1.70 7.60 | 9.00 | 10.80 | 14.60 STA. 10+47 LT **EAST** 30 30 30 SALVAGE SIGN ON NEW POST MONTPELIER VT Route 14 **SALVAGE SIGN ON NEW POST** SPEED LIMIT STA N 11+89 LT 24 30 SALVAGE SIGN ON NEW POST **MONTPELIER** STA N 12+46 LT 21 15 **SALVAGE SIGN ON NEW POST MONTPELIER** 24 SALVAGE SIGN ON NEW POST STA N 13+40 LT 30 6.25 (FLUORESCENT YELLOW SHEETING) MONTPELIER W16-7PL 2.00 (FLUORESCENT YELLOW SHEETING) STA 19+99 RT 30 SALVAGE SIGN ON NEW POST **MONTPELIER** W16-7PL 12 2.00 24 (FLUORESCENT YELLOW SHEETING) STA S 21+61 RT E. Montpelier 72 20 SALVAGE SIGN ON NEW POST Elem. School MONTPELIER FT FT FT LB LB LB LB 0 120 0 FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE." EA. | EA. | LB SF EA. SF FT FT LB EA. LB **TOTALS** 10.25 120 PROJECT NAME: EAST MONTPELIER VILLAGE SAFETY IMPROVEMENT PROJ.

PROJECT NUMBER: STP BIKE (63)

FILE NAME: 622472FItsss.dgn PROJECT LEADER: B. BRESLEND DESIGNED BY: O. DALMER TRAFFIC SIGN SUMMARY SHEET I PLOT DATE: 12/12/2019 DRAWN BY: O. DALMER CHECKED BY: C.LATHROP SHEET 34 OF 44

TRAFFIC SIGN SUMMARY SHEET 2 **AGENCY OF TRANSPORTATION** EXIST POST SIGN DIMENSIONS **NEW & RESETTED SIGNS TUBULAR STEEL** SIGN DETAIL FLANGED CHANNEL SQUARE STEEL (in) W-SHAPE STEEL **MILE MARKER** 3.00 3.50 4.00 5.00 3.00 4.00 4.0 MOD 1.75 | 2.00 | 2.50 POST SIZE STATION OR REMARKS DETAIL DETAIL ON STANDARD RES SIGN RES TIS SIGN NUMBER 24" "A" "B" 30" WIDTH | HEIGHT SHSM NUMBER NUMBER 1.12 | 2.00 | 3.00 | 1.88 | 2.42 | 3.35 1.30 | 1.70 | 1.70 | 7.60 | 9.00 | 10.80 | 14.60 **OPTION ITEMS** STA S 24+11 RT EAST 30 15 30 SALVAGE SIGN ON NEW POST **MONTPELIER** 24 12 SALVAGE SIGN ON NEW POST STA. S 25+07 30 **MONTPELIER** 24 12 SALVAGE SIGN ON NEW POST SALVAGE SIGN ON NEW POST 24 24 SALVAGE SIGN ON NEW POST 21 SALVAGE SIGN ON NEW POST 21 SALVAGE SIGN ON NEW POST STA QR 30+07 Quaker Rd LT EAST 12 42 15 SALVAGE SIGN ON NEW POST MONTPELIER 30 30 SALVAGE SIGN ON NEW POST 1207 SALVAGE SIGN ON NEW POST TSSS 1 TOTAL 120 0 TSSS 2 TOTAL 0.00 10 FT FT FT LB LB LB LB SUBTOTAL 10.25 180 0 0 0 0 0 FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS ROUNDING = 4.75AND THE VTRANS "SIGN POST DESIGN GUIDELINE." SF EA. EA. EA. LB FT FT LB SF LB **TOTALS** 15.00 17. PROJECT NAME: EAST MONTPELIER VILLAGE SAFETY IMPROVEMENT PROJ. PROJECT NUMBER: STP BIKE (63) FILE NAME: 622472FItsss.dgn PLOT DATE: 12/12/2019

PROJECT LEADER: B. BRESLEND

TRAFFIC SIGN SUMMARY SHEET 2


DESIGNED BY: O. DALMER


DRAWN BY: O. DALMER


SHEET 35 OF 44


CHECKED BY: C.LATHROP


STATE OF VERMONT












PROJECT NAME: EAST MONTPELIER VILLAGE SAFETY IMPROVEMENT PROJ.

PROJECT NUMBER: STP BIKE (63)

STA.S 23+50 TO STA.S 25+79

FILE NAME: 622472xs2.dgn
PROJECT LEADER: B.BRESLEND
DESIGNED BY: T.MATTHEWS
CROSS SECTION SHEET 4

PLOT DATE: 12/12/2019
DRAWN BY: T. MATTHEWS
CHECKED BY: C. LATHROP
SHEET 39 OF 44



	ROAD WORK AHEAD	ROAD WORK 500 FT	SIDE ROAD WORK AHEAD	SIDE ROAD WORK 500 FT	PCMS	END ROAD WORK	FLAGGER AHEAD
EAST MONTPELIER							
BEGIN PROJECT- US ROUTE 2	2	2			Ī	I	I
VT ROUTE 14 - WEST INTERSECTION	2	2			Ι	I	
QUAKER RD	I	I				I	
VT ROUTE 14 - NORTH INTERSECTION	2	2			_	I	
END PROJECT - US ROUTE 2	2	2			Ι	I	I
TOTALS	9	9			4	5	2

<u>LEGEND</u>

SRWA = SIDE ROAD WORK AHEAD
SRW500 = SIDE ROAD WORK 500 FT

SRW500 = SIDE ROAD WORK 500 FT RWA = ROAD WORK AHEAD RW500 = ROAD WORK 500 FT

ERW = END ROAD WORK

RWN = ROAD WORK NEXT XX MILES
PCMS = PORTABLE CHANGEABLE MESSAGE SIGN
FLG = FLAGGER AHEAD

NOT TO SCALE

PROJECT NAME: EAST MONTPELIER VILLAGE SAFETY IMPROVEMENT PROJ.

PROJECT NUMBER: STP BIKE (63)

FILE NAME: 622472Floas.dgn
PROJECT LEADER: B.BRESLEND
DESIGNED BY: T.MATTHEWS
CONSTRUCTION APPROACH SIGNING SHEET

PLOT DATE: 12/12/2019

DRAWN BY: T. MATTHEWS

CHECKED BY: C.LATHROP

SHEET 40 OF 44


NOTE:


THE CONTRACTOR SHALL MAINTAIN TWO LANES OF TRAFFIC (ONE EASTBOUND, ONE WESTBOUND) THROUGH THE PROJECT AREA DURING THE PEAK HOURS DEFINED BELOW.

PEAK HOURS:

MONDAY THROUGH FRIDAY
7:00 AM TO 9:00 AM AND 3:00 PM TO 7:00 PM

SATURDAY 9:00 AM TO 6:00 PM





PROJECT NAME: EAST MONTPELIER VILLAGE SAFETY IMPROVEMENT PROJ.

PROJECT NUMBER: STP BIKE (63)

NOT TO SCALE

FILE NAME: 622472FIcas.dgn
PROJECT LEADER: B.BRESLEND
DESIGNED BY: T.MATTHEWS
PHASING TYPICAL SECTION I

PLOT DATE: 12/12/2019

DRAWN BY: T. MATTHEWS

CHECKED BY: C.LATHROP

SHEET 41 OF 44





THE CONTRACTOR SHALL MAINTAIN TWO LANES OF TRAFFIC (ONE EASTBOUND, ONE WESTBOUND) THROUGH THE PROJECT AREA DURING THE PEAK HOURS DEFINED BELOW.

PEAK HOURS:

MONDAY THROUGH FRIDAY
7:00 AM TO 9:00 AM AND 3:00 PM TO 7:00 PM

SATURDAY 9:00 AM TO 6:00 PM





PROJECT NAME: EAST MONTPELIER VILLAGE SAFETY IMPROVEMENT PROJ.

PROJECT NUMBER: STP BIKE (63)

NOT TO SCALE

FILE NAME: 622472FIcas.dgn
PROJECT LEADER: B. BRESLEND
DESIGNED BY: T. MATTHEWS
PHASING TYPICAL SECTION 2

PLOT DATE: 12/12/2019
DRAWN BY: T. MATTHEWS
CHECKED BY: C.LATHROP
SHEET 42 OF 44

CORRIDOR TRAFFIC CONTROL NOTES:

- I. THE CONTRACTOR SHALL SUBMIT A SITE SPECIFIC TRAFFIC CONTROL PLAN PER SUBSECTION 105.03 TO THE ENGINEER. CONSTRUCTION OPERATIONS SHALL NOT COMMENCE UNTIL THE PLAN HAS BEEN APPROVED BY THE ENGINEER. THE CONTRACTOR SHALL INCLUDE A CONSTRUCTION SIGN PACKAGE FOR EXPECTED LANE CLOSURES, WORK ZONE SPEED REDUCTIONS AND PEDESTRIAN ACCESS. THE COST OF PREPARING THIS PLAN (AND MAKING CHANGES IF NECESSARY) WILL BE INCLUDED IN THE UNIT BID PRICE FOR ITEM 641.10, "TRAFFIC CONTROL". THE TRAFFIC CONTROL PLAN SHALL BE IN COMPLIANCE WITH VTRANS STANDARDS AND THE LATEST EDITION OF THE MUTCD. WHERE CONFLICTS EXIST, THE LATEST EDITION OF THE MUTCD SHALL GOVERN.
- THE BID PRICE FOR ITEM 641. II "TRAFFIC CONTROL, ALL-INCLUSIVE", SHALL INCLUDE ALL OF THE FOLLOWING, AS NEEDED: APPROACH AND ON-PROJECT CONSTRUCTION SIGNING, PORTABLE ARROW BOARDS, BARRELS, CONES, BARRICADES, TEMPORARY REGULATORY AND WARNING SIGNS, AND POSTS AS DETAILED IN VAOT STANDARDS. ALL ADJUSTING, RELOCATING, AND REMOVING OF THESE DEVICES AS DIRECTED BY THE ENGINEER SHALL ALSO BE INCLUDED. THE FOLLOWING ITEMS WILL BE PAID FOR SEPARATELY: 646.602 TEMPORARY PAVEMENT MARKINGS 630.10 UNIFORMED TRAFFIC OFFICER, 630.15 FLAGGERS, 641.15 PORTABLE CHANGEABLE MESSAGE SIGN.
- 3. BARRELS, CONES, TEMPORARY TRAFFIC BARRIERS, AND ENERGY ABSORPTION ATTENUATORS SHALL BE USED TO CLEARLY DEFINE THE TRAVEL SPACE AND PROVIDE SEPARATION FROM THE WORK SPACE ALONG ITS ENTIRE LENGTH. REFLECTORIZED CONES WILL BE USED TO DELINEATE COMMERCIAL DRIVES WITHIN THE WORK ZONE.
- 4. THE CONTRACTOR SHALL PROVIDE FLAGGERS FOR ONE LANE TRAFFIC CONTROL, AND AT LOCATIONS WHERE SIGHT DISTANCES ARE IMPAIRED BY CONSTRUCTION OPERATIONS OR OTHER SITUATIONS.
- 5. FLAGGERS SHALL BE REQUIRED TO USE TWO-WAY RADIOS, WALKIE-TALKIES OR OTHER FORMS OF ENHANCED COMMUNICATION WHEN ONE FLAGGER IS NOT VISIBLE TO THE OTHER, OR IF THE ENGINEER DEEMS IT NECESSARY.
- 6. STOP/SLOW PADDLES SHALL BE USED FOR ALL FLAGGING, AND SHALL CONFORM TO THE REQUIREMENTS SET FORTH IN THE MUTCD.
- 7. A MINIMUM LANE WIDTH OF 11 FT. SHALL BE MAINTAINED.
- 8. THE CONTRACTOR SHOULD LEAVE NO LONGITUDINAL DROP-OFFS DURING THE OVERNIGHT HOURS. THEREFORE, THE FULL ROADWAY WIDTH SHOULD BE PAVED DURING THE DAILY WORK PERIOD. WHEN NECESSARY, DROP-OFF PROTECTION IN THESE AREAS SHALL CONFORM TO VAOT STANDARD T-36.
- 9. THE CONTRACTOR SHALL PROVIDE ACCESS THROUGH THE WORK ZONE AND MAINTAIN ACCESS TO ALL PROPERTIES FOR EMERGENCY VEHICLES AT ALL TIMES OR COORDINATE EMERGENCY ROUTES.
- IO. THE CONTRACTOR SHALL NOT PARK EQUIPMENT OR STORE MATERIAL WHERE IT IS DEEMED BY THE ENGINEER TO BE A SAFETY HAZARD.
- II. ANY EXISTING PAVEMENT MARKINGS WHICH CONFLICT WITH THE TRAFFIC CONTROL PLAN SHALL BE REMOVED AS DIRECTED BY THE ENGINEER. THIS WORK SHALL BE PAID UNDER ITEM 641.II (TRAFFIC CONTROL, ALL-INCLUSIVE).
- 12. THE CONTRACTOR SHALL SCHEDULE CONSTRUCTION OPERATIONS IN A MANNER SO AS TO MINIMIZE THE LENGTH OF TIME THAT NORMAL TRAFFIC FLOWS ARE DISTURBED.
- 13. ACCESS TO ALL COMMERCIAL AND MUNICIPAL PROPERTIES SHALL BE MAINTAINED DURING BUSINESS HOURS. ACCESS TO RESIDENTIAL PROPERTIES MAY BE RESTRICTED FOR A SHORT DURATION (A FEW HOURS). THIS WORK SHALL BE COORDINATED WITH THE OWNER/TENANT. COORDINATE MAJOR WORK ON COMMERCIAL OR MUNICIPAL ACCESSES WITH THE OWNER AT LEAST ONE WEEK PRIOR TO STARTING THE WORK. ALL ACCESSES SHALL ALSO BE KEPT FREE OF WORK AND TRAFFIC CONTROLLED BY UNIFORMED TRAFFIC OFFICERS OR FLAGGERS AS REQUIRED BY THE ENGINEER.
- 14. THE CONTRACTOR SHALL MAINTAIN TWO LANES OF TRAFFIC (ONE EASTBOUND, ONE WESTBOUND) THROUGH THE PROJECT AREA DURING PEAK HOURS AS DEFINED IN THE PROJECT SPECIAL PROVISIONS, UNLESS APPROVED IN WRITING BY THE ENGINEER.
- 15. IT IS IMPORTANT THAT CYCLIST ROUTES ARE FREE OF RUTS, SAND, AND MUD TO PREVENT CYCLIST CRASHES. A FOUR (4) FOOT MINIMUM, FIVE (5) FOOT PREFERRED WIDTH SHOULD BE MAINTAINED THROUGH WORK ZONES TO ACCOMODATE BICYCLES WHERE PRACTICAL. IMPLEMENTATION AND EXECUTION OF THIS PRACTICE SHALL BE AT THE DISCRETION OF THE ENGINEER. PAYMENT FOR THIS WORK SHALL BE UNDER ITEM 641.II "TRAFFIC CONTROL, ALL-INCLUSIVE".
- 16. SEE VAOT STANDARD T-10 FOR ADDITIONAL SIGN PLACEMENT DETAILS.
- 17. TRAFFIC SHALL NOT BE CHANGED FROM ONE TRAFFIC PATTERN TO THE NEXT TRAFFIC PATTERN UNTIL ALL TEMPORARY MARKINGS AND SIGNING WORK ARE COMPLETED. ANY CONFLICTING MARKINGS SHALL BE REMOVED.
- 18. THE LATEST EDITION OF THE MUTCD SHALL BE THE STANDARD FOR ALL TRAFFIC CONTROL DEVICES. EXISTING SIGNS AND MARKINGS SHALL BE VALID UNTIL SUCH TIME AS THEY ARE REPLACED OR RECONSTRUCTED. WHEN NEW TRAFFIC CONTROL DEVICES ARE REPLACED OR REPAIRED, THE EQUIPMENT, DESIGN, METHOD OF INSTALLATION, PLACEMENT OR REPAIR SHALL CONFORM WITH SUCH STANDARDS.
- 19. NO CONSTRUCTION SIGNS SHALL BE INSTALLED AS TO INTERFERE OR OBSTRUCT THE VIEW OF EXISTING TRAFFIC CONTROL DEVICES, STOPPING SIGHT DISTANCE, AND CORNER SIGHT DISTANCE FROM DRIVES AND TOWN HIGHWAYS.

- 20. ALL PERMANENT SIGNS THAT CONFLICT WITH TEMPORARY TRAFFIC CONTROL SHALL BE COMPLETELY COVERED, THE PAYMENT FOR WHICH SHALL BE INCLUDED IN THE UNIT PRICE BID FOR ITEM 641. II "TRAFFIC CONTROL, ALL-INCLUSIVE".
- 21. CONSTRUCTION SIGNS SHALL BE IN NEW OR LIKE NEW CONDITION PER VAOT STANDARDS.
- 22. FOR TRAFFIC CONTROL GENERAL NOTES, SEE VAOT STANDARD T-I.
- 23. DIAMOND SHAPED SIGNS SHALL BE 4'X4' WITH BLACK TEXT AND BORDER ON A RETROREFLECTIVE FLUORESCENT ORANGE BACKGROUND.
- 24. ACCOMMODATIONS FOR POSTAL DRIVERS, NEWSPAPER ROUTES, DELIVERY SERVICES AND/OR TRASH SERVICES THAT ARE INTERRUPTED BY THE PROJECT OR DETOUR SHALL BE COORDINATED BY THE CONTRACTOR.
- 25. IF USED, ROADWAY FLAGGER PERSONNEL WILL BE USED TO HOLD AND RELEASE TRAFFIC. ROADWAY FLAGGERS WILL HAVE RECEIVED 4 HOURS OF TRAINING AND SHALL BE CERTIFIED PRIOR TO PERFORMING WORK ON THE PROJECT AND SHALL USE MUTCD COMPLIANT HIGH VISIBILITY APPAREL, SIGN PADDLES, AND TWO WAY RADIOS FOR COMMUNICATION.
- 26. ALTHOUGH THERE ARE NO KNOWN SCHOOL BUS STOP LOCATIONS LOCATED WITHIN THE PROJECT SITE, WHEN SCHOOL IS IN SESSION SCHOOL BUS STOP ACCOMMODATIONS ARE REQUIRED. LOCATIONS SHALL BE COORDINATED WITH THE LOCAL SCHOOL TRANSPORTATION COORDINATOR:

FIRST STUDENT INC. JENNIFER MITCHELL (802)-229-4404 jennifer.mitchell@firstgroup.com

NIGHT WORK:

- I. NIGHT WORK MAY BE REQUIRED TO PERFORM CERTAIN PHASES OF CONSTRUCTION. NIGHT WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE NATIONAL COOPERATIVE HIGHWAY RESEARCH PROGRAM (NCHRP) REPORT 476 "GUIDELINES FOR DESIGN AND OPERATION OF NIGHTTIME TRAFFIC CONTROL FOR HIGHWAY MAINTENANCE AND CONSTRUCTION."
- 2. PRIOR TO ANY NIGHT WORK, A LIGHTING SYSTEM SHALL BE DEVELOPED AND PRESENTED TO THE ENGINEER FOR REVIEW AND ACCEPTANCE; PROVIDE TWO WEEKS IN ADVANCE. NO NIGHT WORK OR ACTIVITES SHALL BE PERFORMED WITHIN THE PROJECT LIMITS UNTIL THE LIGHTING SYSTEM HAS BEEN ACCEPTED AND IN PLACE ON THE PROJECT.

PROJECT NAME: EAST MONTPELIER VILLAGE SAFETY IMPROVEMENT PROJ.

PROJECT NUMBER: STP BIKE (63)

FILE NAME: 622472Fnotes.dgn
PROJECT LEADER: B. BRESLEND
DESIGNED BY: T. MATTHEWS
TRAFFIC CONTROL NOTES SHEET I

PLOT DATE: 12/12/2019
DRAWN BY: T. MATTHEWS
CHECKED BY: C. LATHROP
SHEET 43 OF 44

PEDESTRIAN NOTES

- I. THE CONTRACTOR SHALL PROVIDE A TEMPORARY PEDESTRIAN ACCESS ROUTE (TPAR) FOR REVIEW AND WRITTEN APPROVAL BY THE ENGINEER A MINIMUM OF THREE WEEKS BEFORE SUCH PLAN IS IMPLEMENTED. THIS PLAN SHALL DETAIL THE CONSTRUCTION PHASING AND SCHEDULE AND THE SPECIFIC METHODS OF MAINTAINING SAFE PEDESTRIAN ACCESS THROUGHOUT THE CONSTRUCTION AREA. THIS PLAN SHALL PROVIDE THE LOCATION AND DETAILS OF TEMPORARY CONSTRUCTION SIGNING, MARKINGS, BARRICADES, CHANNELIZING DEVICES, TPARS AND METHODS TO MAINTAIN ACCESS TO ADJACENT PROPERTIES, BUSINESSES, RESIDENCES, ETC.
- 2. THE CONTRACTOR SHALL MAINTAIN PEDESTRIAN THROUGH MOVEMENTS FROM ONE END OF THE CONSTRUCTION AREA TO THE OTHER, ON AT LEAST ONE SIDE OF THE STREET DURING CONSTRUCTION. ANY SIDEWALK CLOSURES SHALL MEET THE REQUIREMENTS OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD) PART 6.
- 3. PEDESTRIAN ACCESS SHALL BE PROVIDED TO ALL ADJACENT PROPERTIES, BUILDINGS, RESIDENCES, COMMERCIAL PROPERTIES AND TRANSIT STOPS. THIS MAY INCLUDE TEMPORARY WALKWAYS SPANNING THE CONSTRUCTION AREA.
- 4. IF SIDEWALKS ARE CLOSED, A TEMPORARY PEDESTRIAN ACCESS ROUTE (TPAR) SHALL BE PROVIDED ON THE SAME SIDE OF THE ROAD AS THE CLOSED SIDEWALK, IF POSSIBLE. SIGNS AND BARRICADES SHALL BE USED TO PROVIDE ADVANCE NOTICE OF THE CLOSURE AND THE ROUTE OF ANY PEDESTRIAN DETOURS. THE TPAR SHALL HAVE A MINIMUM UNOBSTRUCTED WIDTH OF 4 FEET. IF THE TPAR IS LESS THAN 5 FEET IN WIDTH, A 5 FOOT PASSING SPACE MUST BE PROVIDED AT LEAST EVERY 200 FEET. THE SURFACE OF THE TPAR SHALL BE FIRM, STABLE AND SLIP-RESISTANT AND CONTINUOUS WITH A MINIMUM OF 80 INCHES OVERHEAD CLEARANCE FOR THE LENGTH OF THE TPAR. THE TPAR SHALL MAINTAIN THE SAME LEVEL OF ACCESSIBILITY AND DETECTABILITY AS THE FACILITY THAT IS BEING CLOSED. THE TPAR SHALL NOT LEAD PEDESTRIANS INTO CONFLICTS WITH VEHICLES, EQUIPMENT, OR CONSTRUCTION OPERATIONS.
- 5. WHEN TEMPORARY CROSSWALKS ARE UTILIZED FOR THE TPAR, TEMPORARY DETECTABLE WARNINGS SHALL BE PLACED AT EACH END OF THE TEMPORARY CROSSWALKS. THE TEMPORARY CROSSWALK SHALL BE DELINEATED WITH TEMPORARY PAVEMENT MARKINGS OR TAPE. THE MARKINGS SHALL BE PARALLEL 12-INCH-WIDE WHITE LINES PLACED 7 FEET ON CENTER APART. IT SHOULD BE NOTED THAT CURB PARKING SHALL BE PROHIBITED FOR AT LEAST 50 FEET IN ADVANCE OF MIDBLOCK CROSSWALKS. TEMPORARY CROSSWALK SIGNS SHALL BE PROVIDED FOR THE CROSSWALK.
- 6. IF THERE IS WORK OCCURRING OVER AN OPEN SIDEWALK, PROTECTIVE OVERHEAD COVERING MUST BE PROVIDED AS NECESSARY TO ENSURE PROTECTION FROM FALLING OBJECTS AND DRIPPING FROM OVERHEAD STRUCTURES. COVERED WALKWAYS SHOULD BE STURDILY CONSTRUCTED AND ADEQUATELY LIGHTED FOR NIGHT TIME USE.
- 7. INDIVIDUAL CHANNELIZING DEVICES, TAPE, OR ROPE USED TO CONNECT INDIVIDUAL DEVICES AND OTHER DISCONTINUOUS BARRIERS AND DEVICES, PAVEMENT MARKINGS ARE NOT DETECTABLE BY PERSONS WITH VISUAL DISABILITIES. THESE MEASURES DO NOT PROVIDE ACCEPTABLE PATH GUIDANCE ON TEMPORARY OR REALIGNED SIDEWALKS OR OTHER PEDESTRIAN FACILITIES. PEDESTRIAN CHANNELIZING DEVICES SHALL INCLUDE A CONTINUOUSLY DETECTABLE BOTTOM AND TOP EDGE THROUGHOUT THE LENGTH OF THE FACILITY SUCH THAT IT CAN BE FOLLOWED BY PEDESTRIANS USING LONG CANES FOR GUIDANCE.
- 8. CHANNELIZING DEVICES ON BOTH SIDES OF THE TPAR SHALL INCLUDE CONTINUOUS SOLID TOP AND BOTTOM RAILS. THE TOP EDGE OF THE TOP RAIL SHALL BE BETWEEN 32 INCHES AND 38 INCHES ABOVE THE GROUND LEVEL. THE BOTTOM RAIL SHALL BE AT LEAST 6 INCHES WIDE, WITH THE BOTTOM EDGE OF THE BOTTOM RAIL SURFACE NO HIGHER THAN 2 INCHES ABOVE THE GROUND.
- 9. IF THE TPAR IS ADJACENT TO MOVING TRAFFIC, CONSTRUCTION OPERATIONS/EQUIPMENT, OR DROP-OFFS, THEN CRASHWORTHY CHANNELIZING DEVICES THAT MEET THE REQUIREMENTS OF THE MUTCD SHALL BE USED.
- 10. THE CONTRACTOR SHALL NOT STORE OR PLACE ANY CONSTRUCTION MATERIALS, EQUIPMENT, OR SIGNS IN THE PEDESTRIAN PATH OF TRAVEL.
- II. PROVISIONS OF THE TPAR AND ALL ITS ELEMENTS, INCLUDING BUT NOT LIMITED TO SIGNS, CHANNELIZING DEVICES, BARRICADES, TEMPORARY CURB RAMPS, TEMPORARY PAVEMENT MARKINGS AND OTHER TRAFFIC CONTROL DEVICES IS TO BE PAID FOR INCIDENTAL TO ITEM 641. II "TRAFFIC CONTROL, ALL-INCLUSIVE".

NIGHT WORK

I. NIGHT WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE NATIONAL COOPERATIVE HGIHWAY RESEARCH PROGRAM (NCHRP) REPORT 476 - "GUIDELINES FOR DESIGN AND OPERATION OF NIGHTTIME TRAFFIC CONTROL FOR HIGHWAY MAINTENANCE AND CONSTRUCTION". REFER TO THE CONTRACT SPECIAL PROVISION FOR A COMPLETE LIST OF REQUIREMENTS FOR WORKING AT NIGHT. THE CONTRACTOR SHALL SUBMIT A LIGHTING PLAN, INCLUDING EQUIPMENT SPEC SHEETS, TO THE ENGINEER FOR REVIEW A MINIMUM OF 2 WEEKS PRIOR TO NIGHT WORK BEGINNING. ALL COSTS ASSOCIATED WITH THE DESIGN, APPROVAL AND IMPLEMENTATION OF THE LIGHTING SYSTEM WILL BE CONSIDERED INCIDENTAL TO CONTRACT ITEM 641.11 "TRAFFIC CONTROL, ALL-INCLUSIVE."

PROJECT NAME: EAST MONTPELIER VILLAGE SAFETY IMPROVEMENT PROJ.

PROJECT NUMBER: STP BIKE (63)

FILE NAME: 622472Fnotes.dgn
PROJECT LEADER: B. BRESLEND
DESIGNED BY: T. MATTHEWS
TRAFFIC CONTROL NOTES SHEET 2

PLOT DATE: 12/12/2019
DRAWN BY: T. MATTHEWS
CHECKED BY: C. LATHROP
SHEET 44 OF 44