

East Montpelier, TH 1 (County Road) over Mallory Brook (Site 2)

New 77" x 52" x 57' Polymer Coated Steel Pipe Arch with Reinforced Concrete Headwalls

Item No.	Item Name	Quantity	Unit	Unit Price	Total
201.10	Clearing and Grubbing Incl. Individual Trees and Stumps	1	LUMP SUM	\$ 1.00	
203.15	Common Excavation	260	CY	\$ 1.00	
203.27	Unclassified Channel Excavation	15	CY	\$ 1.00	
203.28	Excavation of Surfaces and Pavements	31	CY	\$ 1.00	
203.30	Earth Borrow	180	CY	\$ 1.00	
204.20	Trench Excavation of Earth	25	CY	\$ 1.00	
204.25	Structure Excavation	180	CY	\$ 1.00	
204.30	Granular Backfill for Structures	135	CY	\$ 1.00	
210.10	Cold Planing, Bituminous Pavement	84	SY	\$ 1.00	
301.35	Subbase of Dense Graded Crushed Stone	525	CY	\$ 1.00	
406.25	Bituminous Concrete Pavement	72	TON	\$ 1.00	
501.34	Concrete, High Performance Class B (3500 psi)	20	CY	\$ 1.00	
507.15	Reinforcing Steel	2,230	LBS	\$ 1.00	
514.10	Water Repellent, Silane	10	GAL	\$ 1.00	
601.0910	15" Corrugated Polyethylene Pipe (HDPE)	40	LF	\$ 1.00	
608.25	All Purpose Excavator Rental, Type I	20	HOURS	\$ 1.00	
613.11	Stone Fill, Type II	20	CY	\$ 1.00	
619.20	Removing and Resetting Property Markers	1	EACH	\$ 1.00	
621.20	Steel Beam Guard Rail, Galvanized	620.50	LF	\$ 1.00	
621.60	Anchor for Steel Beam Guard Rail	4	EACH	\$ 1.00	
621.80	Removal and Disposal of Guard Rail	183	LF	\$ 1.00	
635.11	Mobilization/Demobilization	1	LUMP SUM	\$ 1.00	
641.10	Traffic Control	1	LUMP SUM	\$ 1.00	
646.20	4" White Line	140	LF	\$ 1.00	
646.21	4" Yellow Line	140	LF	\$ 1.00	
649.11	Geotextile for Roadbed Separator (for use under new pipe)	60	SY	\$ 1.00	
649.31	Geotextile Under Stone Fill	50	SY	\$ 1.00	
651.40	Grubbing Material	25	SY	\$ 1.00	
	Erosion Prevention and Sediment Control	1	LUMP SUM	\$ 1.00	
	Temporary Stream Diversion	1	LUMP SUM	\$ 1.00	
	Wetlands Restoration Work	1	LUMP SUM	\$ 1.00	
	Installation of New Structure	1	LUMP SUM	\$ 1.00	
	Turf Establishment (Seed, Fertilizer, Mulch, Matting, etc.)	1	LUMP SUM	\$ 1.00	
				Total	