

East Montpelier, TH 1 County Road (Site 1 near Morse Farm) over Brook
New 48" x 51' Polymer Coated Steel Pipe with Reinforced Concrete Headwalls

Item No.	Item Name	Quantity	Unit	Unit Price	Total
201.10	Clearing and Grubbing Incl. Individual Trees and Stumps	1	LUMP SUM	\$ 1.00	
203.15	Common Excavation	234	CY	\$ 1.00	
203.27	Unclassified Channel Excavation	20	CY	\$ 1.00	
203.28	Excavation of Surfaces and Pavements	31	CY	\$ 1.00	
203.30	Earth Borrow	225	CY	\$ 1.00	
204.20	Trench Excavation of Earth	12	CY	\$ 1.00	
204.25	Structure Excavation	149	CY	\$ 1.00	
204.30	Granular Backfill for Structures	130	CY	\$ 1.00	
210.10	Cold Planing, Bituminous Pavement	56	SY	\$ 1.00	
301.35	Subbase of Dense Graded Crushed Stone	430	CY	\$ 1.00	
406.25	Bituminous Concrete Pavement	63	TON	\$ 1.00	
501.34	Concrete, High Performance Class B (3500 psi)	15	CY	\$ 1.00	
507.15	Reinforcing Steel	1,600	LBS	\$ 1.00	
514.10	Water Repellent, Silane	10	GAL	\$ 1.00	
601.0915	18" Corrugated Polyethylene Pipe (HDPE)	52	LF	\$ 1.00	
601.7015	18" Corrugated Polyethylene Pipe End Section (HDPE)	1	EACH	\$ 1.00	
608.25	All Purpose Excavator Rental, Type I	30	HOURS	\$ 1.00	
613.11	Stone Fill, Type II	20	CY	\$ 1.00	
621.20	Steel Beam Guardrail, Galvanized	4	LF	\$ 1.00	
621.60	Anchor for Steel Beam Guard Rail	4	EACH	\$ 1.00	
621.75	Remove and Reset Guardrail (Modified)	487.50	LF	\$ 1.00	
621.76	Replace Guardrail Post Assembly	8	EACH	\$ 1.00	
621.77	Replace Guardrail Beam Unit	9	EACH	\$ 1.00	
635.11	Mobilization/Demobilization	1	LUMP SUM	\$ 1.00	
641.10	Traffic Control	1	LUMP SUM	\$ 1.00	
646.20	4" White Line	140	LF	\$ 1.00	
646.21	4" Yellow Line	140	LF	\$ 1.00	
649.11	Geotextile for Roadbed Separator (for use under new pipe)	46	SY	\$ 1.00	
649.31	Geotextile Under Stone Fill	15	SY	\$ 1.00	
651.40	Grubbing Material	10	SY	\$ 1.00	
				\$ 1.00	
	Erosion Prevention and Sediment Control	1	LUMP SUM	\$ 1.00	
	Temporary Stream Diversion	1	LUMP SUM	\$ 1.00	
	Installation of New Structure	1	LUMP SUM	\$ 1.00	
	Turf Establishment (Seed, Fertilizer, Mulch, Matting, etc.)	1	LUMP SUM	\$ 1.00	
				Total	